To,
Mr. Ali Zahir Shb
DHA Lahore, Pakistan

Date: July 26, 2025
Ref No.: ACCO/DHA/486

Subject: - Quotation for Gray Structure Construction Work Services at DHA Lahore.

السلام علیکم
Dear Sir,

Acco is pleased to submit our best quote for the above-mentioned subject as follows: -

Sr.#	Description	Covered Area	Rate / Sft	Amount (Rs.)	Remarks
1	Ground Floor (Gray Structure)	1478 sft	2,800	4,138,400/-	Structure 10 years warranty
2	First Floor (Gray Structure)	1063 sft	2,800	2,976,400/-	
3	Mumty (Gray Structure)	173 sft	2,800	484,400/-	
	Total cost			**7,599,200/-**	

Total Project Estimate: PKR **7,599,200/-** (**Seven million five hundred ninety-nine thousand two hundred Rupees Only)**

Terms & Conditions:

1. The project completion time is 4 months.
2. Valid for 30 days from the date mentioned.
3. Payment terms as per the defined milestone schedule. Work starts after advance payment.
4. All materials will be finalized with Client's approval. Only standard quality materials will be used.
5. 10-year limited warranty for structure defects after handover.
6. Delays due to weather, strikes, or unforeseen events are not ACCO's responsibility.
7. Any disputes will be resolved through mutual discussion or legal process if required.
8. This quotation is made according to the scope of work provided by the client.
9. Payment shall be made on actual measurement.
10. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
11. Water, Electricity shall be provided by the client.

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Mughal, Ittefaq /Madina Steel, Sj Seteel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

We will be obliged for your Cooperation in this regard.
Thanks & Regards.

Tanveer Ahmed
Director