To,
Mr. Sheikh Ahsan Raza Sahib
DHA Phase VIII, Lahore, Punjab

Date: August 05, 2025
Ref No.: ACCO/DHA/348

**Subject: - QUOTATION FOR CONSTRUCTION OF 8 MARLA COMMERCIAL BUILDING AT DHA PHASE VIII**

السلام علیکم
Dear Sir,

Acco is pleased to submit our best quote for the above-mentioned subject as follows: -

**Grey Structure**

| SR | SCOPE OF WORK | COVERED AREA | RATE /SFT | AMOUNT (Rs) |
|---|---|---|---|---|
| 1 | Basement | 1,800.00 | 5,500.00 | 9,900,000 |
| 2 | Ground Floor | 1,800.00 | 3,500.00 | 6,300,000 |
| 3 | Mezzanine Floor | 1,260.00 | 3,500.00 | 4,410,000 |
| 4 | First Floor | 1,800.00 | 3,500.00 | 6,300,000 |
| 5 | Second Floor | 1,800.00 | 3,500.00 | 6,300,000 |
| 6 | Third Floor | 1,800.00 | 3,500.00 | 6,300,000 |
| 7 | Fourth Floor | 1,800.00 | 3,500.00 | 6,300,000 |
| 8 | Mumty | 250.00 | 3,500.00 | 875,000 |
| | **TOTAL** | **12,310** | | **46,685,000** |

**FINISHING COST**

| SR | SCOPE OF WORK | COVERED AREA | RATE /SFT | AMOUNT (Rs) |
|---|---|---|---|---|
| 1 | Basement | 1,800.00 | 3,500.00 | 6,300,000 |
| 2 | Ground Floor | 1,800.00 | 3,500.00 | 6,300,000 |
| 3 | Mezzanine Floor | 1,260.00 | 3,500.00 | 4,410,000 |
| 4 | First Floor | 1,800.00 | 3,500.00 | 6,300,000 |
| 5 | Second Floor | 1,800.00 | 3,500.00 | 6,300,000 |
| 6 | Third Floor | 1,800.00 | 3,500.00 | 6,300,000 |

| | | | | |
|---|---|---|---|---|
| 7 | Fourth Floor | 1,800.00 | 3,500.00 | 6,300,000 |
| 8 | Mumty | 250.00 | 3,500.00 | 875,000 |
| | **TOTAL** | **12,310** | | **43,085,000** |

**Terms & Conditions:**

1. The project completion time is 4 months.
2. Valid for 30 days from the date mentioned.
3. Payment terms as per the defined milestone schedule. Work starts after advance payment.
4. All materials will be finalized with Client's approval. Only standard quality materials will be used.
5. 10-year limited warranty for structure defects after handover.
6. Delays due to weather, strikes, or unforeseen events are not ACCO's responsibility.
7. Any disputes will be resolved through mutual discussion or legal process if required.
8. This quotation is made according to the scope of work provided by the client.
9. Payment shall be made on actual measurement.
10. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
11. Water, Electricity shall be provided by the client.

**SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE**

| SR | SCOPE OF WORK | COMPONENT / SOURCE /BRAND |
|---|---|---|
| 1 | Excavation in Foundation | Manual or by excavator |
| 2 | Filling | Ghassu Filling |
| 3 | Termite Proofing | Merag/ byflex |
| 4 | Brick Ballast | Brick Or Stone Ballast under Flooring |
| 5 | Lean Concrete 1:4:8 | Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement |
| 6 | P.C.C Concrete 1:2:4 Flooring | Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement |
| 7 | **R.C.C Concrete 1:2:4** | Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement |
| 7-i | Stair | Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement |
| 7-ii | Beams & Slab & Lintels | Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement |
| 8 | Steel | Model , Mughal, Ittefaq /Madina Steel, Sj Seteel |
| 9 | Water Proofing of basement | Water proofing/ Decura water stopper |
| 10 | Brick Masonry | 1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement |
| 11 | Plaster Internal & External in 1:4 | Local Sand, Cherat /DG/Maple leaf Cement |

We will be obliged for your Cooperation in this regard.
Thanks & Regards.

**Tanveer Ahmed**
**Director**