Project Overview:

The existing ICU facility (40x30) is to be upgraded to meet international standards. The upgrade includes installation of various equipment and infrastructure to ensure a safe and efficient environment for patients.

Scope of Work:

1. **Area Size: ICU**
    a. Hall Size 40x30
    b. Corridor buffer Area Size 8x10

Ceiling Installation:
- Installation of HVAC system
- Installation of HEPA filters for 3 glass chambers with a capacity of 3-4 tons, including ducting

2. Public Address System:
- Installation of public speakers for announcements

3. Fire and Smoke Detection System:
- Installation of fire and smoke detection system

4. Dumpa Ceiling:
- Installation of Dumpa ceiling with lights and fans at every bedside for 8-10 beds
- Optional: Grip-o-anticlag system

5. Wall and Flooring:
- Installation of antibacterial sheets on walls (total wall size: 28x9, 40x9, 20x9, 10x9)
- Installation of 2mm vinyl sheet on floor in hall (40x30) and buffer area (8x20)

6. Head Unit and Oxygen Supply:
- Installation of ICU head unit with 2 oxygen ports, 1 port for air, and 4-6 power points (2 high power, one-15 ampere) at every bedside
- Installation of local manifold with 3-4 oxygen cylinders and safety valves

7. Glass Work:
- Installation of 10-12mm tempered glass chambers (2-3 chambers with povit doors)
- Main door: 7x10 glass door with 2 povit doors
- Buffer area: Double door (10x8) for entry and exit

8. Nursing Counter and Accessories:
- Installation of Corian acrylic solid surface nursing counter
- Installation of antibacterial wall guards with antibacterial hand rails

9. Central Nursing Monitoring System:
- Installation of central nursing monitoring system with 7 parameter monitors and IBP, including simple and single pendant for 3 beds in chambers

10. Other Installations:
- Installation of world-class for ICU environment
- Installation of automatic untouched system with/without censors for main entrance door