To,
Mr. Faisal Atta Sahib
Kabul Afghanistan

Date: July 10, 2025
Ref No: ACCO/QTN/473

Subject: - QUOTATION FOR DESIGN OF COMMERCIAL BUILDING AT KABUL

Dear Sir,

Acco is pleased to submit our best quote for subject work as follows: -

Sr.#	Description	Covered Area (Sq Meter)	Rate (Rs.)	Amount (Rs.)
1	Architecture Design (2 Basement + 15 Floors) 60% covered area for each floor according to plot size.	18,247	807/-	14,725,329/-
	Total Cost			14,725,329/-

List of Architectural Design Work

Conceptual Design

- Site analysis and zoning compliance check
- Space planning based on client requirements
- Initial massing and form development
- Preliminary 3D views and diagrams

Schematic Design

- Layouts for all floor types (basement, commercial, residential)
- Apartment typologies (studio, 3-bed, 4-bed, etc.)
- Core design (stairs, lifts, services)
- Preliminary façade concepts
- Rough area statement and basic material palette

Design Development

- Detailed floor plans, sections, and elevations
- Refined façade and material selection
- Parking layout and circulation
- Coordination with structural and MEP consultants
- Updated 3D models/renderings

Construction Drawings

- Complete set of GFC (Good For Construction) drawings
- Detailed plans, sections, elevations for all floors
- Reflected ceiling plans and wall finishes
- Door/window schedules and joinery details
- Typical bathroom and kitchen layouts
- External works layout

Interior Architecture (Optional)

- Standard apartment interior layouts
- Lobbies, corridors, and common areas design
- Commercial area façade and interior concept
- Coordination of furniture layout with MEP

Landscape Design

- Hardscape and softscape for ground and podium levels
- Roof garden or communal terrace if applicable
- Coordination with landscape consultant.

Tender & BOQ Support

- Preparation of architectural BOQ in coordination with QS
- Support in tender documentation related to architectural scope
- Finish schedules and material specs

Site Coordination and Supervision (Optional)

- Periodic site visits for quality checks
- Review of contractor submittals and shop drawings
- Responding to RFIs (Requests for Information)
- Issuing architectural clarifications if required.

Mechanical (HVAC) Scope

- HVAC system design for commercial and residential zones
- Heat load calculations and equipment sizing
- Ventilation for basements, corridors, kitchens, and toilets
- Ducting layout and diffuser placement
- VRF/VRV or split AC system design for apartments

- Chilled water or package units for commercial floors (if applicable)
- Fresh air and exhaust system
- Compliance with ASHRAE and local codes

Electrical Scope

- Electrical load calculations and diversity factor analysis
- Main LT panel, sub-panels, and distribution board layouts
- Power and lighting layout for all floors
- Generator backup integration for common and essential areas
- Earthing & lightning protection system
- Cable routing, conduiting, and riser diagrams
- External and façade lighting design
- Provision for smart metering and automation (optional)

Plumbing & Drainage Scope

- Water supply network design with pumps and storage
- Hot and cold-water distribution system
- Drainage and sewage network with proper venting
- Rainwater harvesting or storm drainage system
- Underground sump and overhead tank design
- Plumbing shafts and access points coordination
- Water meters and isolation valves for individual units

Fire Safety & Life Safety Systems

- Fire detection and alarm system (addressable/manual)
- Fire sprinkler system design as per NFPA/local codes
- Fire hose reel system and fire extinguishers
- Fire pump room with jockey, main, and standby pumps
- Emergency and exit lighting system
- Smoke detectors and heat sensors in critical zones
- Smoke extraction systems for basements
- Pressurization of stairwells and lift lobbies
- Emergency voice evacuation and fireman intercom system
- Compliance with Civil Defense / Fire Authority standards

Lifts & Vertical Transportation

- Passenger lifts for residential floors (minimum 2)
- Dedicated service/stretcher lift
- Commercial zone lift with higher load capacity
- Parking basement lift connectivity
- Elevator control system integration (smart or keycard access)
- Machine room or MRL system coordination
- Fire-rated lift lobbies and rescue provisions
- Lift ventilation and communication system

BMS & Automation

- Centralized Building Management System (BMS)
- Energy monitoring and control systems
- Access control and CCTV integration
- FA system, lighting, and HVAC integration into BMS

Low Current & Communication Systems

- CCTV surveillance system layout
- Telephone/data system with conduits and patch panels
- Intercom system for apartments and security desks
- TV & Satellite system (IPTV or central dish)
- Access control for main entry points

Testing, Commissioning & Handover

- Pre-commissioning and final commissioning of all systems
- Load testing, balancing, and calibration
- Third-party certifications (if required)
- As-built drawings and operation manuals
- Training sessions for client maintenance staff.

Terms & Conditions:

1. This quotation excludes any tax.
2. Payment terms will be decided on agreement
3. Work will start after advance payment.
4. We will be providing A3/A2 size drawings for approval & construction.
5. Completion time for the Project is around 75 days.
6. If the area of the design increases or decreases, the charge will also increase or decrease accordingly.
7. This quotation is valid for 30 days from above mentioned date.
8. Interior Design and Soil Test and Supervision is not included in this quotation.
9. Visit charges will be 100,000/- PKR for every visit.

We will be obliged for your cooperation in this regard.
Thanks & Regards.
Tanveer Ahmed
Director