To,
Mr. Dr. Nasir

Date: July 14, 2025
Ref #: ACCO/QTSN/485

SUBJECT: - **QUOTATION FOR CONSTRUCTION OF GRAY STRUCTURE OF 1 KANAL HOUSE** AT DHA LAHORE.

السلام علیکم
Dear Sir,
We are pleased to submit our best quote for subject work as follows: -

Grey Strcuture

SR	SCOPE OF WORK	COVERED AREA	RATE /SFT	AMOUNT (Rs)
1	BASEMENT (GREY STRUCTURE)	341	4,500.00	1,534,500.00
2	GROUND FLOOR (GREY STRUCTURE)	2,750	2,800.00	7,700,000.00
3	FIRST FLOOR (GREY STRUCTURE)	2,186	2,800.00	6,120,800.00
	TOTAL	**5,277SFT**		**15,355,300.00**

***RATES ARE WITHOUT/EXCLUDING OF ANY TAX**

TERMS & CONDITIONS: -

1. 20% Advance Payment.
2. Bills shall be paid within 3 days after submission.
3. Payment shall be made on actual measurement.
4. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
5. Water, Electricity shall be provided by the client.
6. Completion time 4 Month.

SR	SCOPE OF WORK	Payment Schedule	
		%age	Amount (Rs)
1	MOBLIZATION ADVANCE	20%	3,071,060.00
2	GROUND FLOOR WALLS UPTO PLINTH	15%	2,303,295.00
3	GROUND WALLS	20%	3,071,060.00
4	GROUND SLAB	20%	3,071,060.00
5	FIRST FLOOR WALLS SLAB	20%	3,071,060.00
6	AFTER COMPLETION OF PROJECT	5%	767,765.00
	TOTAL	**100%**	**15,355,300.00**

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Mughal, Ittefaq /Madina Steel, Sj Seteel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

We will be obliged for your Cooperation in this regard.
Thanks & Regards.
Truly yours,

Tanveer Ahmed
Director
+92-322-8000190
Ahmed@acco.com.pk