To,
Mr. Naveed Ebrahim
AGN Pakistan

Date: July 16, 2024
Ref No: ACCO/QTSN/453

**SUBJECT: REVISED QUOTATION FOR CONSTRUCTION OF STOAGE ROOM**

Dear Sir,

We are pleased to submit the requisite Technical & Commercial document for the contractual agreement in accordance with your inquiry and input. The detailed parameters for this job have been mentioned in the sections below.

| Sr. | Description | Quantity | Unit | Rate (PKR) | Amount (PKR) |
|---|---|---|---|---|---|
| 1 | Excavation for wall foundations (3 ft deep, 9" wide) | 1300 | CFT | 12 | 15,600.00 |
| 2 | Earth filling (1.2 ft) | 5550 | CFT | 50 | 277,500.00 |
| 3 | Brick soling (4") | 1831.5 | CFT | 110 | 201,465.00 |
| 4 | PCC 1:4:8 (3" thick) | 1387.5 | CFT | 500 | 693,750.00 |
| 5 | PCC 1:2:4 (4" thick) with Paneling | 1831.5 | CFT | 850 | 1,556,775.00 |
| 6 | Brick masonry in 9" wall (2 long sides, 19 ft high) | 3336 | CFT | 550 | 1,834,800.00 |
| 7 | Internal plaster (both faces) | 6450 | SFT | 60 | 387,000.00 |
| 8 | External plaster (2 long walls) | 3655 | SFT | 65 | 237,575.00 |
| 9 | Roofing structure with Precast Slab and complete Roof tile mud PVC sheet ) | 5984 | SFT | 650 | 3,889,600.00 |
| 1 | Windows & doors lintels precast | 118 | RFT | 1000 | 118,000.00 |
| 10 | MS Windows with grill (6'×4') | 240 | SFT | 1400 | 336,000.00 |
| 11 | MS Sliding Doors (14'×12') 2 Nos | 336 | SFT | 1500 | 504,000.00 |
| 12 | Paint internal and external Distemper | 15800 | SFT | 42 | 663,600.00 |
| 13 | Electric job only labor | 1 | Job | 40000 | 40,000.00 |
| 14 | Plumbing job only labor | 1 | Job | 15000 | 15,000.00 |
| | **TOTAL A** | | | | **10,770,665.00** |
| | **PER SFT COST** | | | | **1,857.97** |

| | | | | | |
|---|---|---|---|---|---|
| | **repairing work of boundary wall & roof treatment** | | | | |
| 14 | repairing of boundary wall with using of old bricks | 950 | SFT | 300 | 285,000.00 |
| 15 | providing & fixing precast columns for boundary wall | 100 | RFT | 900 | 90,000.00 |
| 16 | shall slab repairing in office area | 800 | SFT | 500 | 400,000.00 |
| 17 | External waterproofing | 11000 | SFT | 70 | 770,000.00 |
| | **TOTAL B** | | | | **1,545,000.00** |
| | **GRAND TOTAL (A+B)** | | | | **12,315,665.00** |

**TERMS & CONDITIONS: -**

**MODE OF PAYMENT (Without Taxes):**

1. 20% on the time of start the of work.
2. Bills shall be paid within 7 days of the after the submission.
3. The prices are based on mentioned items in BOQ. Any additional items from BOQ shall be claimed separately.
4. Cordon off Area and Debris removal from site shall be paid for by Client.
5. Provision of all accessibility to working area, Provision of storage facilities for our goods and equipment, where necessary, water & Electricity shall be provided the d by the client.
6. Completion time 1 month.

We will be obliged for your Cooperation in this regard.
With best regards,

Truly yours,

**Tanveer Ahmed**
DIRECTOR