To,
Dr Omar Pervez sahab
Hyderabad, Sindh Pakistan

Date: July 18, 2025
Ref No: ACCO/QTN/HOS480

SUBJECT: - QUOTATION FOR CONSTRUCTION OF OT AT HOSPITAL BUILDING AT HYDERABAD, SINDH PAKISTAN

Dear Sir,

Acco is pleased to submit our best quote for subject work as follows: -

Sr. No	Item Description	Unit	rate (Pkr)	Quantity	Amount (PKR)
	Operation theatre # 1				
1.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	650	285	185,250.00
1.2	**Wall Cladding:** Installation of antibacterial, fire-resistant High-Pressure Laminate (HPL) wall panels, up to 10 feet in height, providing a smooth, durable, and easy-to-clean surface. Edges are sealed for maximum protection against moisture and bacteria.	sft	750	680	510,000.00
1.3	**dampa Ceiling:** made from fungus- and mold-resistant panels, typically aluminum composite or gypsum with antibacterial coating. Easily accessible for maintenance of above-ceiling services.	sft	800	285	228,000.00
	Operation theatre # 2				
2.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	650	330	214,500.00
2.2	**Wall Cladding:** Installation of antibacterial, fire-resistant High-Pressure Laminate (HPL) wall panels, up to 10 feet in height, providing a smooth, durable, and easy-to-clean surface. Edges are sealed for maximum protection against moisture and bacteria.	sft	750	740	555,000.00

2.3	**Dampa Ceiling:** made from fungus- and mold-resistant panels, typically aluminum composite or gypsum with antibacterial coating. Easily accessible for maintenance of above-ceiling services.	sft	800	330	264,000.00
	Operation theatre # 3				
3.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	650	171	111,150.00
3.2	**Wall Cladding:** Installation of antibacterial, fire-resistant High-Pressure Laminate (HPL) wall panels, up to 10 feet in height, providing a smooth, durable, and easy-to-clean surface. Edges are sealed for maximum protection against moisture and bacteria.	sft	750	528	396,000.00
3.3	**Dampa Ceiling:** made from fungus- and mold-resistant panels, typically aluminum composite or gypsum with antibacterial coating. Easily accessible for maintenance of above-ceiling services.	sft	800	171	136,800.00
	Operation theatre # 3				
4.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	650	127.88	83,122.00
4.2	**Wall Cladding:** Installation of antibacterial, fire-resistant High-Pressure Laminate (HPL) wall panels, up to 10 feet in height, providing a smooth, durable, and easy-to-clean surface. Edges are sealed for maximum protection against moisture and bacteria.	sft	750	462	346,500.00
4.3	**Dampa Ceiling:** made from fungus- and mold-resistant panels, typically aluminum composite or gypsum with antibacterial coating. Easily accessible for maintenance of above-ceiling services.	sft	800	127.88	102,304.00

	Lobby Area				
5.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	165	214.6	35,409.00
5.2	**Wall Paint** All surfaces shall be properly cleaned, leveled, and prepared before painting. Apply one coat of alkali-resistant primer followed by two coats of premium-grade low-VOC emulsion paint. The paint must be washable, antibacterial, and antifungal, with a smooth matte or eggshell finish.	sft	100	858	85,800.00
5.3	**Pop Ceiling** The POP surface shall be finished to a smooth, crack-free level using high-quality plaster, with all joints and corners neatly finished.	sft	130	214.6	27,898.00
	Laboratory				
6.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	165	354	58,410.00
6.2	**Wall Paint:** All surfaces shall be properly cleaned, leveled, and prepared before painting. Apply one coat of alkali-resistant primer followed by two coats of premium-grade low-VOC emulsion paint. The paint must be washable, antibacterial, and antifungal, with a smooth matte or eggshell finish.	sft	100	836	83,600.00
6.3	**Pop Ceiling :**The POP surface shall be finished to a smooth, crack-free level using high-quality plaster, with all joints and corners neatly finished.	sft	130	354	46,020.00
	Dressing Room				
7.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	165	390	64,350.00

7.2	**Wall Paint:** All surfaces shall be properly cleaned, leveled, and prepared before painting. Apply one coat of alkali-resistant primer followed by two coats of premium-grade low-VOC emulsion paint. The paint must be washable, antibacterial, and antifungal, with a smooth matte or eggshell finish.	sft	100	860	86,000.00
7.3	**Pop Ceiling :**The POP surface shall be finished to a smooth, crack-free level using high-quality plaster, with all joints and corners neatly finished.	sft	130	390	50,700.00
	Recovery Room				
8.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	165	153.4	25,311.00
8.2	**Wall Paint:** All surfaces shall be properly cleaned, leveled, and prepared before painting. Apply one coat of alkali-resistant primer followed by two coats of premium-grade low-VOC emulsion paint. The paint must be washable, antibacterial, and antifungal, with a smooth matte or eggshell finish.	sft	100	498	49,800.00
8.3	**Pop Ceiling :**The POP surface shall be finished to a smooth, crack-free level using high-quality plaster, with all joints and corners neatly finished.	sft	130	153.4	19,942.00
	Lobby 2				
9.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	165	372.3	61,429.50
9.2	**Wall Paint:** All surfaces shall be properly cleaned, leveled, and prepared before painting. Apply one coat of alkali-resistant primer followed by two coats of premium-grade low-VOC emulsion paint. The paint must be washable, antibacterial, and antifungal, with a smooth matte or eggshell finish.	sft	100	1168	116,800.00
9.3	**Pop Ceiling :**The POP surface shall be finished to a smooth, crack-free level using high-quality plaster, with all joints and corners neatly finished.	sft	130	372.3	48,399.00

	Pre-Entrance				
10.1	**Flooring tiles** shall be high-quality, first-grade porcelain or ceramic tiles, minimum 8mm thick, anti-slip, stain-resistant, and suitable for Pre entrance.	sft	500	160	80,000.00
10.2	**Wall Paint:** All surfaces shall be properly cleaned, leveled, and prepared before painting. Apply one coat of alkali-resistant primer followed by two coats of premium-grade low-VOC emulsion paint. The paint must be washable, antibacterial, and antifungal, with a smooth matte or eggshell finish.	sft	100	560	56,000.00
10.3	**Pop Ceiling :**The POP surface shall be finished to a smooth, crack-free level using high-quality plaster, with all joints and corners neatly finished.	sft	130	160	20,800.00
	Laminar Air Flow Unit Air Flow Type: Vertical Laminar Flow Air Velocity: 90–120 FPM (feet per minute) Filtration System: Pre-filters: EU-5 / G4 Grade (washable) HEPA Filters: H-14 grade, 99.995% efficiency @ 0.3 microns Plenum Material: Stainless Steel 304, powder-coated Size: Custom-sized to OT dimensions (typically 2400mm x 2400mm or as per drawing) Noise Level: < 65 dB(A) at 1 meter Standards Compliance: EN 1822 / ISO 14644-1 (Clean Room Class 5 or better) ASHRAE / HTM 03-01 guidelines for healthcare ventilation Accessories: Pressure differential gauge HEPA filter access hatch Integration with modular ceiling system	NOS	2000000	4	8,000,000.00
	Providing and Fixing of Ducting	SFT	650	800	520,000.00
	Total				12,149,294.50

Terms & Conditions:

1. This quotation excludes any tax.
2. The advance 60% in advance, 30% on the material at site and 10% on the completion of project.
3. Work will start after advance payment.
4. If the area of the design increases or decreases, the charge will also increase or decrease accordingly.
5. This quotation is valid for 30 days from above mentioned date.

We will be obliged for your cooperation in this regard.

Thanks & Regards.
Tanveer Ahmed
Director