To,
Mr. Mukhtiar Ahmed Sahib
Lake City, Lahore

Date: August 19, 2025
Ref #: ACCO/QTSN/471

SUBJECT: - **QUOTATION FOR REMOVAL OF EXISTING PLASTER & RE-PLASTERING WORK** AT LAKE CITY LAHORE.

السلام علیکم
Dear Sir,
We are pleased to submit our best quote for subject work as follows: -

SR	SCOPE OF WORK	COVERED AREA (SFT)	RATE /SFT	AMOUNT (Rs)
1	REMOVAL OF EXISTING PLASTER	7,000	25.00	175,000.00
2	NEW PLASTER APPLICATION CEMENT: BESTWAY / DG CEMENT SAND: CHENAB SAND THICKNESS: ½" (12 MM) RATIO: 1:3 (CEMENT : SAND)	7,000	95.00	665,000.00
	TOTAL	**7,000SFT**		**840,000.00**

***RATES ARE WITHOUT/EXCLUDING OF ANY TAX**

TERMS & CONDITIONS: -

1. 50% Advance Payment.
2. Bills shall be paid within 3 days after submission.
3. Payment shall be made on actual measurement.
4. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
5. Water, Electricity shall be provided by the client.
6. Completion time 15 Days.

We will be obliged for your Cooperation in this regard.
Thanks & Regards.
Truly yours,

Tanveer Ahmed
Director
+92-322-8000190
Ahmed@acco.com.pk