To,
Mr. Mohammad Masoom Zafar Sahib
Park View City Lahore, Punjab

Date: August 29, 2025
Ref No: ACCO/QTN/538

Subject: - QUOTATION FOR DESIGN & CONSTRUCTION OF COMMERCIAL BUILDING AT PARK VIEW CITY LAHORE

Dear Sir,

Acco is pleased to submit our best quote for subject work as follows: -

Sr.#	Description	Covered Area (Sqft)	Rate (Rs.)	Amount (Rs.)
1	Architecture Design of Commercial Plaza (1 Basement + Mezzanine + 5 Floors + Mumty)	8,125	Lum Sump	120,000/-
	Total Cost			**120,000/-**

Grey Structure

Sr.#	Description	Covered Area (Sqft)	Rate (Rs.)	Amount (Rs.)
1	Basement	1,125	5,500.00	6,187,500.00
2	Mezzanine Floor	562.5	4,000.00	2,250,000.00
3	Ground Floor	1,125	4,000.00	4,500,000.00
4	First Floor	1,125	4,000.00	4,500,000.00
5	Second Floor	1,125	4,000.00	4,500,000.00
6	Third Floor	1,125	4,000.00	4,500,000.00
7	Fourth Floor	1,125	4,000.00	4,500,000.00
8	Mumty	250	4,000.00	1,000,000.00
	TOTAL COST	**8,125**		**31,937,500.00**

List of Architectural Design Work

Conceptual Design

- Site analysis and zoning compliance check
- Space planning based on client requirements
- Initial massing and form development
- Preliminary 3D views and diagrams

Schematic Design

- Layouts for all floor types (basement, commercial)
- Core design (stairs, lifts, services)
- Preliminary façade concepts
- Rough area statement and basic material palette

Design Development

- Detailed floor plans, sections, and elevations
- Refined façade and material selection
- Parking layout and circulation
- Coordination with structural and MEP consultants
- Updated 3D models/renderings

Construction Drawings

- Complete set of GFC (Good For Construction) drawings
- Detailed plans, sections, elevations for all floors
- Reflected ceiling plans and wall finishes
- Door/window schedules and joinery details
- Typical bathroom and kitchen layouts
- External works layout

Interior Architecture (Optional)

- Standard apartment interior layouts
- Lobbies, corridors, and common areas design
- Commercial area façade and interior concept
- Coordination of furniture layout with MEP

Mechanical (HVAC) Scope

- HVAC system design for commercial and residential zones
- Heat load calculations and equipment sizing
- Ventilation for basements, corridors, kitchens, and toilets
- Ducting layout and diffuser placement
- VRF/VRV or split AC system design for apartments
- Chilled water or package units for commercial floors (if applicable)
- Fresh air and exhaust system
- Compliance with ASHRAE and local codes

Electrical Scope

- Electrical load calculations and diversity factor analysis
- Main LT panel, sub-panels, and distribution board layouts
- Power and lighting layout for all floors
- Generator backup integration for common and essential areas
- Earthing & lightning protection system
- Cable routing, conduiting, and riser diagrams
- External and façade lighting design
- Provision for smart metering and automation (optional)

Plumbing & Drainage Scope

- Water supply network design with pumps and storage
- Hot and cold-water distribution system
- Drainage and sewage network with proper venting
- Rainwater harvesting or storm drainage system
- Underground sump and overhead tank design
- Plumbing shafts and access points coordination
- Water meters and isolation valves for individual units

Fire Safety & Life Safety Systems

- Fire detection and alarm system (addressable/manual)
- Fire sprinkler system design as per NFPA/local codes
- Fire hose reel system and fire extinguishers
- Fire pump room with jockey, main, and standby pumps

- Emergency and exit lighting system
- Smoke detectors and heat sensors in critical zones
- Smoke extraction systems for basements
- Pressurization of stairwells and lift lobbies
- Emergency voice evacuation and fireman intercom system
- Compliance with Civil Defense / Fire Authority standards

Lifts & Vertical Transportation

- Passenger lifts for residential floors (minimum 2)
- Dedicated service/stretcher lift
- Commercial zone lift with higher load capacity
- Parking basement lift connectivity
- Elevator control system integration (smart or keycard access)
- Machine room or MRL system coordination
- Fire-rated lift lobbies and rescue provisions
- Lift ventilation and communication system

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Mughal, Ittefaq /Madina Steel, Sj Seteel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

Terms & Conditions:

1. The project completion time is 45 Days for design and 6 Month for grey structure.
2. Valid for 30 days from the date mentioned.
3. Payment terms as per the defined milestone schedule. Work starts after advance payment.
4. All materials will be finalized with Client's approval. Only standard quality materials will be used.
5. 15-year limited warranty for structure defects after handover.
6. Delays due to weather, strikes, or unforeseen events are not ACCO's responsibility.
7. Any disputes will be resolved through mutual discussion or legal process if required.
8. Payment shall be made on actual measurement.
9. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
10. Water, Electricity shall be provided by the client.
11. This quotation excludes any tax.
12. We will be providing A3 size drawings for approval & construction.
13. If the area of the design increases or decreases, the charge will also increase or decrease accordingly.
14. Interior Design and Soil Test and Supervision is not included in this quotation.

We will be obliged for your cooperation in this regard.
Thanks & Regards.
Tanveer Ahmed
Director