To,
Dr. Moeez ul haq
Imram idress Teaching Hospital Sialkot

Date: Sept 19, 2025
Ref No: ACCO/QTN/HOS648

SUBJECT: - QUOTATION FOR CONSTRUCTION OF OPERATION THEATERS AT TEACHING HOSPITAL SIALKOT

Dear Sir,

Acco is pleased to submit our best quote for subject work as follows: -

Sr. No	Item Description	Unit	Nos	rate (Pkr)	Quantity	Amount (PKR)
	Operation theatre 3 Nos (21'-6"x20'-9")					
1.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	3	750	445	1,001,250.00
1.2	**Wall Cladding:** Installation of **Lamiguard wall cladding system** consisting of antibacterial, fire-resistant, termite-resistant, anti-scratch, anti-fungal, and water-resistant panels. Panels are mounted up to 10 feet in height on, ensuring strength and durability. The system provides a smooth, seamless, and easy-to-clean surface suitable for high-performance environments. All panel edges are properly sealed to achieve maximum protection against moisture ingress and bacterial growth.	sft	3	1850	850	1,572,500.00
1.3	**Dampa Ceiling:** made from fungus- and mold-resistant panels, typically aluminum composite or gypsum with antibacterial coating. Easily accessible for maintenance of above-ceiling services.	sft	3	700	445	311,500.00
	Operation theatre (18'-0"x26'-9")					
2.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	1	750	470	352,500.00

2.2	**Wall Cladding:** Installation of **Lamiguard wall cladding system** consisting of antibacterial, fire-resistant, termite-resistant, anti-scratch, anti-fungal, and water-resistant panels. Panels are mounted up to 10 feet in height on, ensuring strength and durability. The system provides a smooth, seamless, and easy-to-clean surface suitable for high-performance environments. All panel edges are properly sealed to achieve maximum protection against moisture ingress and bacterial growth.	sft	1	1850	900	1,665,000.00
2.3	**Dampa Ceiling:** made from fungus- and mold-resistant panels, typically aluminum composite or gypsum with antibacterial coating. Easily accessible for maintenance of above-ceiling services.	sft	1	700	470	329,000.00
	Operation theatre (21'-0"x21'-0")					
3.1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	sft	1	750	448	336,000.00
3.2	**Wall Cladding:** Installation of **Lamiguard wall cladding system** consisting of antibacterial, fire-resistant, termite-resistant, anti-scratch, anti-fungal, and water-resistant panels. Panels are mounted up to 10 feet in height on, ensuring strength and durability. The system provides a smooth, seamless, and easy-to-clean surface suitable for high-performance environments. All panel edges are properly sealed to achieve maximum protection against moisture ingress and bacterial growth.	sft	1	1850	880	1,628,000.00
3.3	**Dampa Ceiling:** made from fungus- and mold-resistant panels, typically aluminum composite or gypsum with antibacterial coating. Easily accessible for maintenance of above-ceiling services.	sft	1	700	448	313,600.00
	DOORS					

4.1	Providing & fixing antibacterial sliding door **304 stainless steel**, complete with heavy-duty track system, rollers, handles, and all necessary hardware. The door shall be smooth in operation, corrosion-resistant, durable, and easy to clean, ensuring hygienic performance for healthcare and cleanroom applications.	sft	5	240,000		1,200,000.00
	Total					**8,709,350.00**

Terms & Conditions:

1. This quotation excludes any tax.
2. The advance 60% in advance, 30% on the material at site and 10% on the completion of project.
3. Work will start after advance payment.
4. If the area of the design increases or decreases, the charge will also increase or decrease accordingly.
5. This quotation is valid for 30 days from above mentioned date.

We will be obliged for your cooperation in this regard.

Thanks & Regards.

Tanveer Ahmed
Director