To,
Mr. Inzamam Ul Haq Sahab
Procurement Officer
Sitara Chemical Industries Limited, Faisalabad

Date: September 29, 2025
Ref: ACCO/QTSN/655

SUBJECT: - **QUOTATION FOR CONSTRUCTION OF COOLING TOWER AT SCIL FAISALABAD**

We are pleased to submit our best quote for subject work as follows: -

SR	SCOPE OF WORK	AMOUNT (Rs)
1	CIVIL CONSTRUCTION WORKS	21,399,848/-
	TOTAL	**21,399,848/-**

TERMS & CONDITIONS: -

1. Rates of excluding of all Taxes.
2. 20% Advance Payment.
3. Bills shall be paid within 3 days after submission.
4. Payment shall be made on actual measurement.
5. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
6. Water, Electricity shall be provided by client.
7. The project timeline shall be mutually agreed upon. Any delays caused by the client, including approvals, site access, or provision of required facilities, may result in revised completion schedules and additional costs.
8. The payment schedule shall be mutually agreed upon before the commencement of work.

We will be obliged for your Cooperation in this regard.
Thanks & Regards.
Truly yours,

Tanveer Ahmed
Director
+92-322-8000190
ahmed@acco.com.pk

SITARA CHEMICAL INDUSTRIES LTD FAISALABAD

Construction of New Cooling Tower 02 Cell (1600m3 per hour)

Bill of Quantities

S.No	Description	Unit	Quantity	Unit Rate	Amount
1	**Earth Work**				
	Excavation for foundation as per drawings and specification to all lifts and leads, in any kind of soil including , soling , sandy, silty, clayey, moist or damp soil of any hardness as per drawings and back filling (in layer not exceeding 6" in thickness, dressing watering and consolidation by mechanical means full compaction) specification and to the entire satisfaction of the Engineer.	Cum	500.47	403.50	201,939
2	**Sand Filling**			-	-
	Supplying, stacking and Filling Chanab sand conforming to specification approved by the Engineer and filling under floor as shown on the drawing in layer not exceeding 6" in thickness, dressing watering and consolidation by mechanical means full compaction as per specifications and to the entire satisfaction of the Engineer.	Cum	156.60	1,143.25	179,029
3	**P.C Concrete**			-	-
i	Providing and laying, straight or curved cast-in place Plain cement concrete cylinder crushing strength 1000 psi, using S.R. cement including Form work, vibrating through electro mechanical vibrator, levelling, compacting and curing as per specifications and to the entire satisfaction of the Engineer.	Cum	33.29	6,213.90	206,868
ii	Providing, laying, compacting, levelling , trovelling , top finishing & curing plain cement concrete cylinder crushing strength 3000 psi, using O.P cement including form work where required dividing into panels and top smooth top finish. complete in all respects conforming to the requirements of drawings and specification and to the entire satisfaction of the Engineer.	Cum	3.19	8,473.50	27,054

SITARA CHEMICAL INDUSTRIES LTD FAISALABAD					
Construction of New Cooling Tower 02 Cell (1600m3 per hour)					
Bill of Quantities					
S.No	**Description**	**Unit**	**Quantity**	**Unit Rate**	**Amount**
4	**Reinforced Cement Concrete**				-
a	Providing and laying, straight or curved cast-in place designed mix reinforced structural cement concrete cylinder crushing strength 3000 psi, using S.R. cement including water proofing chemical , chemical resistant chemical of Sika or equivalent , Formwork , vibrating through electro mechanical vibrator, levelling, compacting, curing, placing of all pipes, sleeves, conduits and fittings, with necessary arrangements where required and other embedded items before concreting . complete in all respects conforming to the requirements of drawings and specification and to the entire satisfaction of the Engineer.				-
i	Foundation	Cum	68.10	10,087.50	687,007
b	Providing and laying, straight or curved cast-in place designed mix reinforced structural fair finish cement concrete cylinder crushing strength 3750 psi, using S.R. Cement in sub structure and O.P. cement in super structure including water proofing chemical , chemical resistant chemical of Sika or equivalent, Formwork, vibrating through electro mechanical vibrator, levelling, compacting, curing, placing of all pipes, sleeves, conduits and fittings, with necessary arrangements where required and other embedded items before concreting . complete in all respects conforming to the requirements of drawings and specification and to the entire satisfaction of the Engineer.			-	-
i	Walls and Column	Cum	162.29	14,189.75	2,302,863
ii	Beams	Cum	48.20	12,992.70	626,304
iii	Slab	Cum	21.00	12,992.70	272,852
iv	Stair	Cum	15.10	12,992.70	196,151

SITARA CHEMICAL INDUSTRIES LTD FAISALABAD

Construction of New Cooling Tower 02 Cell (1600m3 per hour)

Bill of Quantities

S.No	Description	Unit	Quantity	Unit Rate	Amount
v	Floor	Cum	16.21	12,992.70	210,622
5	**Steel Reinforcement**				-
	Providing, fabricating and fixing in position grade 60 reinforcing bars (Fazal, Ambrelly, Afco) of any size of any diameter with 60,000 lbs per sq. inch yield strength including the cost of straightening cutting , wastage and such overlaps as are not shown on the drawings in position on M.S. Chairs or 1:2 precast concrete chairs tying in all kinds of reinforced concrete and in any position at any level or elevations or at any height and any position conforming to the requirement of drawings and specifications, complete in all respects. Waste, lappage and rolling margin shall be on contractor account. Steel test report for every lot must be done jointly.	Kg	41,363.50	327.50	13,546,545
6	**PVC water stopper**				-
	Providing and fixing in position 250mm wide and 6mm thick PVC water stopper of approved quality as per drawings specifications complete in all respects and as additionally directed by the consultant engineer.	RM	62.04	2,870.00	178,055
7	**M.S Work**				-
	Providing and laying in position M.S plates with anchores built or ebbeded into as per drwaing. specifications complete in all respects and as additionally directed by the consultant engineer.	Kg	983.00	625.00	614,375
8	**Rubber Coating**				-
	Providing and applying polyurethane of ICI KEMOBEL CHLORINATED RUBBER FINISH (Chlorinated Rubber Finish CR 05) or equivalent as per technical data , specifications and to the entire satisfaction of the Engineer.				-
i	Concrete	SM	2,955.51	201.75	596,274

SITARA CHEMICAL INDUSTRIES LTD FAISALABAD					
Construction of New Cooling Tower 02 Cell (1600m3 per hour)					
Bill of Quantities					
S.No	**Description**	**Unit**	**Quantity**	**Unit Rate**	**Amount**
9	**Hi-Build Zinc Rich Epoxy Primer EC 11**				-
	Providing and applying polyurethane of ICI Hi-Build Zinc Rich Epoxy Primer EC 11 Two Pack Zinc Rich Polyamide Cured Organic Primer EC 11 application and coats as per technical data , specifications and to the entire satisfaction of the Engineer.				-
i	Steel Reinforcement	Kg	41,363.50	18.75	775,566
10	**UPVC Pipe**				
	Providing, laying, fixing and testing B Class uPVC pipe including uPVC fittings with solvent cement jointing or rubber ring joints Master, Popular or equivalent make as approved by the Engineer In charge complete in all respects, including, clamps, bends, tees, Y-tees, cowls, reducers, clean out etc., embedded in floors and walls, clamped to walls, suspended from slab, painted MS horizontal and vertical pipe hangers of approved design making requisite no. of holes and making good the same complete in all respects.				
i	6” dia	RM	158.20	4,920.00	778,344
	Total Amount Rs				**21,399,848**
Notes:					
1	1-Cement= DG , Lucky , Askari , 2-Crush = Sargodha , Margalla , 3- Sand = Concrete 50% Lawrencepur and 50% Chenab. Plastering Chenab pure fine)				
2	All types of necessary testing like Steel, Bricks, aggregates, Cement, Slump, cylinder, compaction tests etc and any other tests will be carried out and will be submitted to Client.				
3	Contractor will submit the sample / shop drawing for approval before fabrication / installation of any item. The rates include the cost of all samples / shop drawing.				