To,
Ar.Waleed Ahmad Khan

Date: July 18, 2025
Ref No: ACCO/QTN/HOS688

SUBJECT: - QUOTATION FOR CONSTRUCTION OF OT MATERIAL AT HOSPITAL BUILDING AT PESHAWER KPK.

Dear Sir,

Acco is pleased to submit our best quote for subject work as follows: -

Sr. No	Item Description	Unit	Rate (PKR)	Quantity	Amount (PKR)
Operation theatres (7 Nos)					
1	Vinyl Flooring: High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, resistant to chemicals and stains.	sft	850	2278	1936300
2	HPL Wall Cladding: Installation of antibacterial, fire-resistant High-Pressure Laminate wall panels (up to 10' height). Smooth, durable, and easy-to-clean surface with sealed edges for maximum protection against moisture and bacteria.	sft	1850	5545	10258250
3	Dampa Ceiling: Fungus- and mold-resistant aluminum composite/gypsum panels with antibacterial coating. Provides easy access to above-ceiling services.	sft	650	2278	1480700
Sterilize Area					
4	Vinyl Flooring: High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, resistant to chemicals and stains.	sft	850	234	198900
5	HPL Wall Cladding: Installation of antibacterial, fire-resistant High-Pressure Laminate wall panels (up to 10' height). Smooth, durable, and easy-to-clean surface with sealed edges for maximum protection against moisture and bacteria.	sft	1850	660	1221000

6	Dampa Ceiling: Fungus- and mold-resistant aluminum composite/gypsum panels with antibacterial coating. Provides easy access to above-ceiling services.	sft	650	234	152100
Equipment Store					
7	Vinyl Flooring – Equipment Store	sft	850	200	170000
8	HPL Wall Cladding – Equipment Store	sft	1850	590	1091500
9	Dampa Ceiling – Equipment Store	sft	650	200	130000
Recovery Room					
10	Vinyl Flooring – Recovery Room	sft	850	710	603500
11	HPL Wall Cladding – Recovery Room	sft	1850	1116	2064600
12	Dampa Ceiling – Recovery Room	sft	650	710	461500
Doors (Stainless Steel – SS204)					
13	OT Main Door (5'-0"x7'-0"): Heavy-duty stainless steel SS204 main OT doors, hermetically sealed, antibacterial, rust-proof, and durable.	Nos	220000	7	1540000
14	OT Side Door (3'-0"x7'-0"): Single-leaf SS204 stainless steel door for OT side entry, hygienic, rust-proof, and seamless.	Nos	195000	5	975000
15	OT Store Door (2'6"x7'-0"): Compact stainless steel SS204 store door, smooth and antibacterial finish.	Nos	175000	8	1400000
16	Equipment Store Door (5'-0"x7'-0"): Strong SS204 stainless steel door with antibacterial and rust-free surface.	Nos	220000	1	220000
17	Recovery Room Door (5'-0"x7'-0"): Stainless steel SS204 recovery room door, ensuring hygienic patient environment.	Nos	220000	1	220000
18	Sterilize Area Door (5'-0"x7'-0"): Hermetic stainless steel SS204 sterilize area door, durable and antibacterial.	Nos	220000	2	440000
Scrub Area					

19	Sink (SS): High-grade stainless-steel sinks for scrub area, rust-free, antibacterial, easy-to-clean surface, suitable for hygiene-critical use.	Nos	95000	3	285000
	Grand Total:				**24,848,350.00**

Terms & Conditions:

1. **Scope of Work**
   - This quotation covers supply and installation of vinyl flooring, HPL wall cladding, dampa ceilings, stainless steel doors (SS204), and stainless-steel sinks as per specifications mentioned in the BOQ.
   - Any additional work beyond the listed scope will be charged separately.
2. **Exclusions**
   - Government taxes, duties, and levies are excluded and will be charged as applicable at the time of billing.
   - Electrical, plumbing, HVAC, and civil works are not included unless specified.
   - **Transportation of materials to the site is not included in this quotation and will be charged separately.**
3. **Payment Terms**
   - 50% advance payment upon confirmation of order.
   - 40% payment during execution, based on work progress.
   - 10% payment upon final completion and handing over.
4. **Validity of Quotation**
   - This quotation is valid for **30 days** from the date of issue.
   - Prices are subject to change after the validity period.
5. **Execution Timeline**
   - Work commencement will be within **3–5 working days** after receipt of advance payment.
   - Completion timeline will be mutually agreed based on site readiness and work front availability.
6. **Material Specifications**
   - All materials supplied will be as per specifications mentioned in the BOQ.
   - Substitutions, if any, will be approved in writing by the client before procurement.
7. **Warranty**
   - One-year warranty against manufacturing defects for doors, flooring, and wall cladding.
   - Warranty does not cover misuse, mishandling, or damage due to third-party works.
8. **Site Conditions**

- The client shall ensure that the site is ready, clean, and free from obstructions before commencement of works.
- Adequate storage space, electricity, and water supply must be provided by the client.

9. **Supervision**
    - A site supervisor/engineer will monitor the execution to ensure quality and compliance with specifications.
10. **Force Majeure**

- The contractor will not be liable for delays due to events beyond reasonable control, such as natural disasters, strikes, or government restrictions.

We will be obliged for your cooperation in this regard.

Thanks & Regards.

Tanveer Ahmed
Director