To,
Dr. Muhammad Asadullah Khan
Zohra Medical and Surgical Complex, Shakargarh

Date: Oct 13, 2025
Ref No: ACCO/QTN/413

SUBJECT: - QUOTATION FOR CONSTRUCTION OF OPERATION THEATER SHAKARGARH

Dear Sir,

Acco is pleased to submit our best quote for subject work as follows: -

Sr.	Item Description	Unit	Nos	Rate	Quantity	Amount
	Operation theatre 1 Nos (16'-7"x12'-6")					
1.1	**Vinyl Flooring:** Supply and Installation of High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains complete in all respect.	sft	1	750	210	157,500.00
1.2	**Wall Cladding:** Supply and Installation of wall cladding system consisting of antibacterial, fire-resistant, termite-resistant, anti-scratch, anti-fungal, and water-resistant panels. Panels are mounted up to 10 feet in height on, ensuring strength and durability. The system provides a smooth, seamless, and easy-to-clean surface suitable for high-performance environments. All panel edges are properly sealed to achieve maximum protection against moisture ingress and bacterial growth complete in all respect.	sft	1	1665	2070	3,446,550.00
1.3	**Dampa Ceiling:** Made from fungus- and mold-resistant panels, typically aluminum composite with antibacterial coating. Easily accessible for maintenance of above-ceiling services complete in all respect.	sft	1	650	210	136,500.00
	DOORS					
4.1	Providing & fixing antibacterial sliding door **304 stainless** steel, complete with heavy-duty track system, rollers, handles, and all necessary hardware. The door shall be smooth in operation, corrosion-resistant, durable, and easy to clean, ensuring hygienic performance for healthcare and cleanroom applications complete in all respect.	sft	1	225,000		225,000.00
	Total					**3,965,550.00**

Terms & Conditions:

1. This quotation excludes any tax.
2. The advance 60% in advance, 30% on the material at site and 10% on the completion of project.
3. Work will start after advance payment.
4. If the area of the design increases or decreases, the charge will also increase or decrease accordingly.
5. This quotation is valid for 30 days from above mentioned date.

We will be obliged for your cooperation in this regard.

Thanks & Regards.

Tanveer Ahmed
Director