To,
Hafiz Adil Raza

Date: October 10, 2025
Ref No: ACCO/QTN/768

Subject: - QUOTATION FOR DESIGN OF HOUSE DESGIN AT DHA PHASE 4

Dear Sir,

Acco is pleased to submit our best quote for subject work as follows: -

Sr.#	Description	Covered Area (Sqft)	Rate (Rs.)	Amount (Rs.)
1	Architecture Design of House Design (Ground & First floor + Mumty) Plot Size: 9 Marla	4,100 SFT	25	102,500/-
	Total Cost			**102,500/-**

Scope of Work / Deliverables

1. **3D Elevation Views**
   Realistic 3D renderings showcasing the external appearance and aesthetics of the building.
2. **Furniture Layout Plans**
   Detailed layout plans indicating furniture placement for optimal space utilization.
3. **Architectural Drawings**
   Complete set of architectural plans including floor plans, sections, and elevations.
4. **Structural Drawings**
   Detailed structural layout and reinforcement details.
5. **Public Health Drawings**
   Plumbing and sanitary layout including water supply, drainage, and vent systems.
6. **Electrical Drawings**
   Power layout, lighting design, and circuit distribution plans.
7. **Submission Drawings**
   Complete set of drawings prepared as per DHA / local authority bylaws, including site plan, floor plans, elevations, sections, and relevant details required for approval.

Grey Structure

SR	SCOPE OF WORK	COVERED AREA	RATE /SFT	AMOUNT (Rs)
1	GROUND FLOOR (GREY STRUCTURE)	1,900.00	2,850.00	5,415,000
2	FIRST FLOOR +MUMTY (GREY STRUCTURE)	2,200.00	2,850.00	6,270,000
	TOTAL	**4,100**		**11,685,000**

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Ittefaq /Madina Steel, Sj Seteel, Agha Steel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

Terms & Conditions

Design Services

1. **Payment Terms:** 50% advance payment is required to initiate the design work. The remaining 50% will be charged in two equal installments during the design process.
2. **Commencement:** Work will commence only after receipt of the advance payment.
3. **Drawing Format:** A3-size drawings will be provided for approval and construction purposes.
4. **Completion Timeline:** The estimated design completion time is **20 days** from the date of commencement.
5. **Area Variations:** If the design area increases or decreases, the total cost will be adjusted accordingly.
6. **Quotation Validity:** This quotation is valid for **30 days** from the date mentioned above.
7. **Exclusions:** Interior design, soil testing, and site supervision are **not included** in this quotation.

Construction Services

8. **Advance Payment:** 30% advance payment is required before starting construction work.
9. **Billing & Payment:** Bills shall be submitted periodically and must be paid within **7 days** of submission.
10. **Measurement Basis:** Payments will be made based on **actual measurements** at the site.
11. **Warranty:** A **5-year structural warranty** is provided from the date of project completion.
12. **Additional Items:** Prices are based on the specified items only. Any additional work or items will be charged separately. The client shall provide suitable storage space for materials, equipment, and tools, where necessary.
13. **Utilities:** Water and electricity required for construction shall be provided by the client.
14. **Quotation Validity:** This construction quotation is valid for **30 days** from the date of issuance.

We will be obliged for your cooperation in this regard.
Thanks & Regards.
Tanveer Ahmed
Director