To,
Ms. Shagufta,
Phase 8, DHA Lahore

Date: October 31, 2025
Ref: ACCO/DHA/H/814

SUBJECT: - **QUOTATION FOR DESIGN & CONSTRUCTION OF 1 KANAL HOUSE AREA (50X90 FEET)** AT PHASE 8, DHA LAHORE.

We are pleased to submit our best quote for subject work as follows: -

Design

SR	SCOPE OF WORK	COVERED AREA	RATE /SFT	AMOUNT (Rs)
1	GROUND FLOOR	2,773	30.00	83,190/-
2	FIRST FLOOR	2,254	30.00	67,620/-
	TOTAL	**5,027**		**150,810/-**

Grey Structure

SR	SCOPE OF WORK	COVERED AREA	RATE /SFT	AMOUNT (Rs)
2	GROUND FLOOR (GREY STRUCTURE)	2,773	2,800/-	7,764,400
3	FIRST FLOOR + MUMTY (GREY STRUCTURE)	2,254	2,800/-	6,311,200
	TOTAL	**5,027**		**14,075,600/-**

Finishing Cost

SR	SCOPE OF WORK	COVERED AREA	RATE /SFT	AMOUNT (Rs)
2	GROUND FLOOR (GREY STRUCTURE)	2,773	4,500/-	12,478,500/-
3	FIRST FLOOR + MUMTY (GREY STRUCTURE)	2,254	4,500/-	10,143,000/-
	TOTAL	**5,027**		**22,621,500/-**

TERMS & CONDITIONS: -

1. Rates of excluding of all Taxes.
2. 30% Advance Payment.
3. Bills shall be paid within 3 days after submission.
4. Payment shall be made on actual measurement.
5. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
6. Water, Electricity shall be provided by client.
7. The project timeline shall be mutually agreed upon. Any delays caused by the client, including approvals, site access, or provision of required facilities, may result in revised completion schedules and additional costs.
8. The payment schedule shall be mutually agreed upon before the commencement of work.
9. The design cost will be refunded if the entire project is awarded.
10. If the permission from the authorities on company then extra 150,000/- will be charged form the submission of drawings and get the all NOC's and permissions.
11. The charges for finishing are just as per A+ standard this cost may be increase or decrease as material for finishing if changed.

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Ittefaq /Madina Steel, Sj Seteel, Agha Steel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

We will be obliged for your Cooperation in this regard.
Thanks & Regards.
Truly yours,

Tanveer Ahmed
Director