To,
Dr Zahid Sheikh

Date: November 09, 2025
Ref No: ACCO/QTN/865

SUBJECT: - QUOTATION FOR INSTALLATION OF LUMINAR AIRFLOW SYSTEM

Dear Sir,

Acco is pleased to submit our best quote for subject work as follows: -

1. Laminar air flow system

Sr.#	Description	Area (SFT)	Rate (Rs.)	Amount (Rs.)
1	Providing and fixing of laminar airflow system Size: 8'x8'x14" SS 201 Complete setup with Hepa filter (1'x1') complete in all respect	64	6,000/-	384,000/-
2	AH (Air Handling Unit) Local manufacturer Warranty: 2 years	4 (Ton)	200,000/-	800,000/-
3	Duct (Size: as per site)	1	650/-	650/-
4	Control Panel (Flow control complete in all respect)	1	350,000/-	350,000/-
	Total Cost			**1,534,650/-**

2. Operation Theater Material (22'-3"x21'-0")

Sr.#	Description	Area (SFT)	Rate (Rs.)	Amount (Rs.)
1	**Vinyl Flooring:** High-performance, antibacterial, seamless vinyl flooring designed for hygiene-critical environments. Heat-welded joints ensure no gaps for microbial growth, and the surface is resistant to chemicals and stains	472	1000/-	472,000/-
2	**Wall Cladding:** Installation of antibacterial, fire-resistant High-Pressure Laminate (HPL) wall panels, up to 10'-6" feet in height, providing a smooth, durable, and easy-to-clean surface. Edges are sealed for maximum protection against moisture and bacteria.	914	2250/-	2,056,500/-
3	**Dampa Ceiling:** made from fungus- and mold-resistant panels, typically aluminum composite or gypsum with antibacterial coating. Easily accessible for maintenance of above-ceiling services.	472	650/-	306,800/-
4	**OT Door (4'-0"x7'-0"):** Heavy-duty stainless steel SS204 main OT doors, hermetically sealed, antibacterial, rust-proof, and durable.	28	-	250,000/-
	Total Cost			**3,085,300/-**

Terms & Conditions:

1. **Completion time:** The project completion time is 20 days.
2. **Quotation Validity:** Valid for 30 days from the date mentioned.
3. **Payment:** As per the defined in the agreement. Work starts after advance payment.
4. **Force Majeure:** Delays due to weather, strikes, or unforeseen events are not ACCO's responsibility.
5. **Disputes:** Any disputes will be resolved through mutual discussion or legal process if required.
6. This quotation is made according to the scope of work provided by the client.
7. If the area of the design increases or decreases, the charge will also increase or decrease accordingly.

We will be obliged for your cooperation in this regard.

Thanks & Regards.
Tanveer Ahmed
Director