To,
Mr. Aftab Awan Sahib
DHA Lahore, Punjab

Date: November,18 2025
Ref No: ACCO/QTN/958

Subject: - QUOTATION FOR DESIGN & CONSTRUCTION OF COMMERCIAL BUILDING AT DHA LAHORE

Dear Sir,

Acco is pleased to submit our best quote for subject work as follows: -

Sr.#	Description	Covered Area (Sqft)	Rate (Rs.)	Amount (Rs.)
1	Structure Design of Commercial Plaza (1 Basement + Ground + 4 Floors + Mumty)	12,200	15/-	183,000/-
	Total Cost			**183,000/-**

Sr.#	Description	Covered Area (Sqft)	Rate (Rs.)	Amount (Rs.)
1	Basement	1,800	6,000/-	10,800,000/-
2	Ground Floor	1,800	4,500/-	8,100,000/-
3	First Floor	1,800	4,500/-	8,100,000/-
4	Second Floor	1,800	4,500/-	8,100,000/-
5	Third Floor	1,800	4,500/-	8,100,000/-
6	Fourth Floor	1,800	4,500/-	8,100,000/-
7	Mumty	400	4,500/-	1,800,000/-
	TOTAL COST	**12,200**		**53,100,000/-**

List of Structural Design Work

- Detailed floor plans, sections, and elevations
- Refined façade and material selection
- Parking layout and circulation
- Coordination with structural and MEP consultants

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Mughal, Ittefaq /Madina Steel, Sj Seteel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

Terms & Conditions:

1. Valid for 30 days from the date mentioned.
2. Payment terms as per the defined milestone schedule. Work starts after advance payment.
3. All materials will be finalized with Client's approval. Only standard quality materials will be used.
4. 15-year limited warranty for structure defects after handover.
5. Delays due to weather, strikes, or unforeseen events are not ACCO's responsibility.
6. Any disputes will be resolved through mutual discussion or legal process if required.
7. Payment shall be made on actual measurement.
8. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
9. Water, Electricity shall be provided by the client.
10. This quotation excludes any tax.
11. If the area of building increases or decreases, the charge will also increase or decrease accordingly.

We will be obliged for your cooperation in this regard.
Thanks & Regards.
Tanveer Ahmed
Director