THE UNIVERSITY OF LAHORE

THE UNIVERSITY OF LAHORE

DRAINAGE WORK FOR ROAD AND PARKING AT NEW LAND

BILL OF QUANTITY

Sr.No	Description	Unit	Qty	Rate		Amount			Remarks
				Supply	Services	Supply	Services	Total	
A	**DRAINS (D1,D2,D3,D4)**								
1	**EXCAVATION**								
	Excavation of Foundation in all kind of soil (including gravelly, clay or mud conglomeration of gravel or boulders, soft, sandy or disintegrated sandy & hard rock etc.) upto required depth for foundation etc. Complete as directed by the Engineer In charge.	Cft	132044		15/-		1980660/-	1980660/-	
2	**P.C.C (1:4:8)**								
	Providing, and laying cement concrete not leaner than (1:4:8) using Chenab Sand and Sargodha crushed stone graded aggregate 3/4 inch (19 mm) and down gauge in foundations including compacting, levelling and curing etc. complete as directed by the Engineer In charge.	Cft	2169	400/-	100/-	867600/-	216900/-	1084500/-	
3	**R.C.C DRAINS**								
	Providing and laying concrete, having a 28 days cylinder strength of 4000Psi by Weigh Batch with water-cement ratio not more than 0.50 and cement content not to be less than 425Kg per cubic meter and using electromechanical vibrators, Sargodha Crush of approved size and gradation and clean 100% Lawrencepur Sand of approved quality with Admixture Ultra sp 470, including curing etc. Cost of steel reinforcement is excluded.								
	Foundation	Cft	3822	850/-	350/-	3248700/-	1337700/-	4586400/-	
	Walls	Cft	8403	850/-	450/-	7142550/-	3781350/-	10923900/-	
	Top Slab	Cft	3822	850/-	450/-	3248700/-	1719900/-	4968600/-	
4	**STEEL REINFORCEMENT**								
	Providing, cutting, fabricating, and fixing in position mild steel deformed reinforcement bars of Grade-60 as per ASTM A615, having a minimum yield strength of 60,000 PSI. The scope includes the cost of cleaning, straightening, cutting, bending, and binding with 12 SWG annealed binding wire, including the provision of steel chairs, spacers, and all accessories required for maintaining cover in RCC works. All works shall be completed as per approved drawings, specifications, and instructions of the Engineer-in-Charge.	Kg	31714	260/-	55/-	8245640/-	1744270/-	9989910/-	
5	**FILLING OF CRUSH STONE**								
	Providing and laying crush stone of approved quality under the Rcc Pipe, including all leads and lifts, complete in all respects as directed by the Engineer In-Charge.	Cft	10333	180/-	40/-	1859940/-	413320/-	2273260/-	
6	**R.C.C PIPE 24" DIAMETER**								
	Providing and laying R.C.C. pipe sewers, molded with cement concrete 1:1½:3 conforming to ASTM Specification C-76-79, Class III, Wall B, including carriage of pipes from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipe where necessary, testing, etc. complete.	Rft	1349	3000/-	1500/-	4047000/-	2023500/-	6070500/-	
7	**CIRCULAR MANHOLE**								
	Construction of circular masonry manhole of 5 ft. dia (Type - B) for 18" to 30" sewer size having following depths including manhole HDPE cover of and frame, rungs, complete in all respects as per drawings and as Directed by the Engineer.								
	upto 6 depth	No,s	35		140,000/-		4900000/-	4900000/-	
	upto 9 depth	No,s	6		200,000/-		1200000/-	1200000/-	
8	**GHASSU FILLING**								
	Supplying and filling Ghassu River material from all leads and lifts, including digging, loading, unloading, and filling under foundations, etc., along with watering and consolidation by ramming in layers with proper compaction (payment based on compacted measurement only). The work shall be completed as per drawings, specifications, and as directed by the Engineer.	Cft	113828	45/-	20/-	5122760/-	2276560/-	7398820/-	
B	**DISPOSAL WELL AND CULVERT**								
a)	**EXCAVATION**								
	Excavation in any type of soil including, stacking of serviceable and un-serviceable materials separately with in project boundary, upholding the sides of the excavation, keeping excavation free from water, Backfill and disposal of surplus material as directed by the Engineer , as per drawings and all in accordance with the specifications.	Cft	28258		15/-		423870/-	423870/-	



THE UNIVERSITY OF LAHORE

THE UNIVERSITY OF LAHORE

DRAINAGE WORK FOR ROAD AND PARKING AT NEW LAND

BILL OF QUANTITY

Sr.No	Description	Unit	Qty	Rate		Amount			Remarks
				Supply	Services	Supply	Services	Total	
b)	**P.C.C (1:4:8)**								
	Providing, and laying cement concrete not leaner than (1:4:8) using Chenab Sand and Sargodha crushed stone graded aggregate 3/4 inch (19 mm) and down gauge in foundations including compacting, levelling and curing etc. complete as directed by the Engineer In charge.	Cft	356	400/-	100/-	142,400/-	35600/-		
c)	**R.C.C CULVERT & WELL**								
	Providing and laying concrete, having a 28 days cylinder strength of 4000Psi by Weigh Batch with water-cement ratio not more than 0.50 and cement content not to be less than 425Kg per cubic meter and using electromechanical vibrators, Sargodha Crush of approved size and gradation and clean 100% Lawrencepur Sand of approved quality with Admixture Ultra sp 470, including curing etc. Cost of steel reinforcement is excluded.								
	Foundation	Cft	993	850	350	844050/-	347550/-	1191600/-	
	Walls	Cft	1487	850	450	1263950/-	669150/-	1933100/-	
	Top Slab	Cft	771	850	450	655350/-	346950/-	1002300/-	
d)	**WATER STOPPER**								
	Providing & Embedding 9" wide 9mm~10mm thick PVC water stopper (mar flex) or equivalent along all construction joints complete as per drawings specification and instruction of the Engineer In charge.	Rft	230	350/-	80/-	80500/-	18400/-	98900/-	
e)	**BITUMEN COATING**								
	Providing and Applying hot bitumen coating (Two Coat) @ 34 Lbs /% sft with sand spraying on RCC Surface, complete in all respects and as directed by The Engineer.	Sft	3294	80/-	50/-	263520/-	164700/-	428220/-	
f)	**COMPACTED GRANULAR MATERIAL**								
	Providing & Laying and spreading Granular Material upto any thickness and of any size between 3" to 3/4" in Sub base or base course in required grade as and where required i/c camber and compacting to the specified density by approved mechanical means into (vibratory roller, road packer and smooth wheel roller etc.,) i/c stone dust filling , watering with all lead and left complete into (actual compacted depth shall be considered for payment)	Cft	9419	140/-	40/-	1318660/-	376760/-	1695420/-	
g)	**STEEL REINFORCEMENT**								
	Providing, cutting, fabricating, and fixing in position mild steel deformed reinforcement bars of Grade-60 as per ASTM A615, having a minimum yield strength of 60,000 PSI. The scope includes the cost of cleaning, straightening, cutting, bending, and binding with 12 SWG annealed binding wire, including the provision of steel chairs, spacers, and all accessories required for maintaining cover in RCC works. All works shall be completed as per approved drawings, specifications, and instructions of the Engineer-in-Charge.	Kg	9638	260/-	55/-	2505880	530090/-	3035970/-	
					TOTAL AMOUNT:				

40,856,700/- 24507239/- (65363930/-)

PRA 16% 10458229/-

Total 75822159/-

THE UNIVERSITY OF LAHORE

The University of Lahore

EXISTING ROAD WORK NEW LAND (SOL-1)

BILL OF QUANTITY

Sr.No	Description	Unit	Qty	Rate		Amount			Remarks
				Supply	Services	Supply	Services	Total	
1	**ROAD MILLING**								
	Removal of existing asphalt or concrete surface using a milling machine to the required depth, including collection and disposal of milled material, surface cleaning, and preparation for new pavement. Work to be completed in all respects as per drawings, specifications, and Engineer's instructions.	Sft	41860.00		30/-		1255800/-	1255800/-	
1	**BASE COURSE (WBM)**								
	Providing and laying Base Course of crushed stone of approved quality, including the cost of Stone dust with placing, mixing, spreading, watering and compacting base course to required depth in **Two Layers**, camber and grade to achieve 100% maximum modified AASHTO dry density conforming to AASHTO specification T - 180, with mechanical means and with all lead and lift. as per drawings and all in accordance with the specifications or as directed by the Engineer.	Cft	41860.00	180/-	45/-	7534800/-	1883700/-	9418500/-	
2	**PRIME COAT**								
	Providing And Applying Bituminous Priming Coat, Using 10Lbs, Kerosene Oil And 10 Lbs, Binder Per 100 Sft Or 0.5 Kg Kerosene And 0.5 Kg Binder Per Sq.M.	Sft	83720.00	40/-	20/-	3348800/-	1674400/-	5023200/-	
3	**ASPHALTIC BASE (2" THICK)**								
	Providing And Laying Plant Premixed Asphaltic Base Course, Including Compaction And Finishing To Required Camber, Grade, And Density (C) 2" (50 Mm) Thick,	Sft	83720.00	250/-	96/-	20930000/-	8037120/-	28967120/-	
4	**BITUMINOUS TACK COAT**								
	Providing And Laying Bituminous Tack Coat, Using 10 Lbs. Of Bitumen Per 100 Sft (0.49 Kg Of Bitumen Per Sq.M.)	Sft	83720.00	40/-	20/-	3348800/-	1674400/-	5023200/-	
5	**ASPHALTIC WEARING COURSE**								
	Providing And Laying Plant Premixed Bituminous Carpet (Asphaltic Wearing Course), Including Compaction And Finishing To Required Camber, Grade And Density As Per Approved Job-Mix Formula (C) 1.5" (38 mm) Think,	Sft	83720.00	280/-	66/-	23441600/-	5525520/-	28967120/-	
6	**SUB BASE**								
	Providing and laying Sub Base using natural source crushed Stone aggregate of approved thickness to required grade and camber in (**Two Layers**) layers to achieve 95% maximum modified AASHTO dry density conforming to AASHTO specification T - 180 including watering, comapcting with mechanical means and with all lead and lift. as per drawings and all in accordance with the specifications or as directed by the Engineer.	Cft	5532.19	150/-	45/-	829800/-	248940/-	1078740/-	
7	**KERB STONE**								
	Fixing precast edge kerb stone (12"x6"x14") of IZHAR, including the cost of setting, jointing and pointing in CM 1:4 with embedded in PCC (1:2:4) over lean concrete (1:4:8), complete in all respects. **Kerb Stone will Supplied by Client.**	Rft	1475.45		70/-	+	1032815/-	1032815/-	
8	**TUFF PAVER**								
	Laying Tuff Pavers 2.5mm thick, having 7000 PSI, crushing strength, including the cost of 1.5" Ravi Sand Cushion with grouting in joints i/c finishing to require slope. Complete in all respect and as directed by The Engineer. **Paver will be Supplied by Client.**	Sft	8257.00		25/-		206875/-	206875/-	
					TOTAL AMOUNT:				

59433800/- 20610037/- (80043837/-)

PRA. 16% 12807014/-

92850850/-

Total



THE UNIVERSITY OF LAHORE

THE UNIVERSITY OF LAHORE

PARKING AREA AT NEW LAND

BILL OF QUANTITY

Sr.No	Description	Unit	Qty	Rate		Amount			Remarks
				Supply	Services	Supply	Services	Total	
1	**CLEANING GRUBBING & NGC**								
	Cleaning Grubbing + Compaction of Natural Ground with more than 95% modified AASHTO Density complete in all respect as per drawings and specifications	Sft	431178		8/-		3,449,424/-	3,449,424/-	
2	**SUB-GRADE**								
	Subgrade work in ordinary soil, including ploughing and mixing with blade grad or disc harrow or other suitable equipment, and compaction by mechanical means at optimum moisture content and dressing to designed section, complete in all respects: 95% of maximum modified AASHO to T-180 density (Min CBR =8%).	Cft	470455		29/-		13,643,195/-	13,643,195/-	
3	**SUB-BASE**								
	Providing and laying of Sub-Base course of stone product of approved quality and grade in two layers, including placing, mixing, spreading and compaction of sub-base material to required depth, grade to achieve 98% maximum modified AASHO dry density, including carriage of all material to site of work. Complete in all respect and as directed by The Engineer.	Cft	288889	150/-	45/-	43333350/-	13000005/-	56,333,355/-	
4	**TUFF PAVER**								
	Laying Tuff Pavers 2.5mm thick, having 7000 PSI, crushing strength, including the cost of 1.5" Ravi Sand Cushion with grouting in joints i/c finishing to require to require slope. Complete in all respect and as directed by The Engineer. **Paver will Supplied by Client.**	Sft	403232		25/-		10080800/-	10080800/-	
5	**KERB STONE**								
	Fixing precast edge kerb stone (12"x6"x14") of IZHAR, including the cost of setting, jointing and pointing in CM 1:4 with embedded in PCC (1:2:4) over lean concrete (1:4:8), complete in all respects. **Kerb Stone will Supplied by Client.**	Rft	14988		70/-		1049160/-	1049160/-	
6	**TOE WALL**								
a)	Excavation in any type of soil including, stacking of serviceable and un-serviceable materials separately with in project boundary, upholding the sides of the excavation, keeping excavation free from water, Backfill and disposal of surplus material as directed by the Engineer , as per drawings and all in accordance with the specifications.	Cft	5072		15/-		76080/-	76080/-	
b)	Providing, and laying cement concrete not leaner than (1:4:8) using Chenab Sand and Sargodha crushed stone graded aggregate 3/4 inch (19 mm) and down gauge in foundations including compacting, levelling and curing etc. complete as directed by the Engineer Incharge.	Cft	1203	400/-	100/-	481200/-	120300/-	601500/-	
c)	Providing and laying first class solid burnt brick masonry, set in cement mortar (1:6) for Foundation including curing etc. Complete in all respect or as directed by the Engineer in charge.	Cft	6428	450/-	70/-	2892600/-	449960/-	3342560/-	
d)	Providing 3/4" thick cement plaster (1:4) on soffits of slabs, beams, slabs & Walls etc., in any floor including making edges, corners, all plaster to be finished smooth with steel float in true level, line and plumb and properly cured and scaffolding etc. Complete as directed by the Engineer Incharge.	Sft	15976	50/-	25/-	798950/-	399475/-	1198425/-	
e)	Supplying and filling ordinary soil source of all leads and lifts including, digging, loading and unloading and filling in under foundation etc. including watering and consolidation by ramming in layers with compaction, as per drawings and all in accordance with the specifications or as directed by the Engineer.	Cft	1808	45/-	20/-	81360/-	36160/-	117520/-	
	TOTAL AMOUNT					47587460/-	42304559/-	89892019/-	

PRA 16%. 14382723/-

104274742/-

THE UNIVERSITY OF LAHORE

THE UNIVERSITY OF LAHORE

ROAD WORK NEW LAND (SOL-2)

BILL OF QUANTITY

Sr.No	Description	Unit	Qty	Rate		Amount			Remarks
				Supply	Services	Supply	Services	Total	
1	**CLEANING GRUBBING & NGC**								
	cleaning grubbing including compaction of natural ground with more than 95% modified aashto density. incldluing the cost of disposal of unsuitable debris from site. complete in all respect and as directed by the engineer.	Sft	92511		8/-		740088/-	740088/-	
2	**CUTTING OF SOIL**								
	Cutting surplus material and disposing of unsuitable material outside the project area, while stacking suitable material along the roadway or other designated area, in accordance with the sections, grades, and specifications shown in the drawings.	Cft	115368		17/-		196256/-	196256/-	
3	**EMBANKMENTS**								
	Earthwork in ordinary soil for embankments lead up to 100 ft (30 m), including ploughing, mixing, and compaction by mechanical means at optimum moisture content and dressing to designed section, complete in all respects. for 95% to 100% maximum modified aashto dry density (subgrade i/c)	Cft	384275		23/-		8838325/-	8838325/-	
4	**SUB BASE**								
	Providing and laying Sub Base using natural source crushed Stone aggregate of approved thickness to required grade and camber in **(Two Layers)** layers to achieve 95% maximum modified AASHTO dry density conforming to AASHTO specification T - 180 including watering, comapcting with mechanical means and with all lead and lift. as per drawings and all in accordance with the specifications or as directed by the Engineer.	Cft	62765	150/-	45/-	9414750/-	2824425/-	12239175/-	
5	**BASE COURSE (WBM)**								
	Providing and laying Base Course of crushed stone of approved quality, including the cost of Stone dust with placing, mixing, spreading, watering and compacting base course to required depth in **Two Layers**, camber and grade to achieve 100% maximum modified AASHTO dry density conforming to AASHTO specification T - 180, with mechanical means and with all lead and lift. as per drawings and all in accordance with the specifications or as directed by the Engineer.	Cft	35439	180/-	45/-	6379020/-	1594755/-	7973775/-	
6	**PRIME COAT**								
	Providing and applying bituminous priming coat, using 10lbs, kerosene oil and 10 lbs, binder per 100 sft or 0.5 kg kerosene and 0.5 kg binder per sq.m.	Sft	42697	40/-	20/-	1707880/-	853940/-	2561820/-	
7	**ASPHALTIC BASE (2" THICK)**								
	Providing And Laying Plant Premixed Asphaltic Base Course, Including Compaction and Finishing To Required Camber, Grade, And Density (C) 2" (50 Mm) Thick,	Sft	42697	250/-	96/-	10674250/-	4098912/-	14773162/-	
8	**BITUMINOUS TACK COAT**								
	Providing and Laying Bituminous Tack Coat, Using 10 Lbs. Of Bitumen Per 100 Sft (0.49 Kg Of Bitumen Per Sq.M.)	Sft	42697	40/-	20/-	1707880/-	853940/-	2561820/-	
9	**ASPHALTIC WEARING COURSE**								

THE UNIVERSITY OF LAHORE

THE UNIVERSITY OF LAHORE

ROAD WORK NEW LAND (SOL-2)

BILL OF QUANTITY

Sr.No	Description	Unit	Qty	Rate		Amount			Remarks
				Supply	Services	Supply	Services	Total	
	Providing and laying plant premixed bituminous carpet (asphaltic wearing course), including compaction and finishing to required camber, grade and density as per approved job-mix formula (c) 1.5" (38 mm) think,	Sft	42697	280/-	66/-	11,955,160/-	2,818,002/-	14,773,162/-	
10	**KERB STONE**								
	Fixing precast edge kerb stone (12"x6"x14") of IZHAR, including the cost of setting, jointing and pointing in CM 1:4 with embedded in PCC (1:2:4) over lean concrete (1:4:8), complete in all respects. **Kerb Stone will Supplied by Client.**	Rft	7733		70/-		541,310/-	541,310/-	
11	**TUFF PAVER**								
	Laying Tuff Pavers 2.5mm thick, having 7000 PSI, crushing strength, including the cost of 1.5" Ravi Sand Cushion with grouting in joints i/c finishing to require slope. Complete in all respect and as directed by The Engineer. **Paver will be Supplied by Client.**	Sft	49203		25/-		1230075/-	1230075/-	
12	**TOE WALL**								
a)	Excavation in any type of soil including, stacking of serviceable and un-serviceable materials separately with in project boundary, upholding the sides of the excavation, keeping excavation free from water, Backfill and disposal of surplus material as directed by the Engineer , as per drawings and all in accordance with the specifications.	Cft	5361		15/-		80,415/-	80,415/-	
b)	Providing, and laying cement concrete not leaner than (1:4:8) using Chenab Sand and Sargodha crushed stone graded aggregate 3/4 inch (19 mm) and down gauge in foundations including compacting, levelling and curing etc. complete as directed by the Engineer Incharge.	Cft	1325	400/-	100/-	530,000/-	132,500/-	662,500/-	
c)	Providing and laying first class solid burnt brick masonry, set in cement mortar (1:6) for Foundation including curing etc. Complete in all respect or as directed by the Engineer in charge.	Cft	6804	450/-	70/-	3061,800/-	476,280/-	3538,080/-	
d)	Providing 3/4" thick cement plaster (1:4) on soffits of slabs, beams, slabs & Walls etc., in any floor including making edges, corners, all plaster to be finished smooth with steel float in true level, line and plumb and properly cured and scaffolding etc. Complete as directed by the Engineer Incharge.	Sft	11545	50/-	25/-	571,250/-	288,625/-	865,875/-	
e)	Supplying and filling ordinary soil source of all leads and lifts including, digging, loading and unloading and filling in under foundation etc. including watering and consolidation by ramming in layers with compaction, as per drawings and all in accordance with the specifications or as directed by the Engineer.	Cft	1857	45/-	20/-	83565/-	37140/-	120,705/-	
					TOTAL AMOUNT:		46091,555/-	27369,188/-	(73461,543/-)

Ahmed Construction Company ACCO

PRA 16% 11,753,847/-

Total 85,215,390/-