To,
Mr Aaqib Usman

Date: April 03, 2026
Ref No: ACCO/QTSN/1552

SUBJECT: - QUOTATION FOR ICU OF SIALKOT MEDICAL COMPLEX AT SIALKOT.

Sr	Category	Item Description	Unit	Qty	Rate	Amount	Remarks
1	**Ceiling**	**Dumpa Ceiling (ICU Hall)** • The ceiling suspension system shall be made of galvanized steel U-profile attached to the concrete ceiling via threaded rod and clamping brackets with the flexibility of adjusting the ceiling height. • The clamping rails where the ceiling cassettes will be fixed in are attached to the suspension system via galvanized connectors. • The ceiling cassettes shall be 600 x 0.7 mm made of Aluminum. The visible part shall be powder coated with polyurethane in RAL 9010.	sqft	1200	650	780,000	Grid ceiling system
2	**Ceiling**	**Dumpa Ceiling (Buffer Area)**	sqft	80	650	52,000	
3	**HVAC**	HVAC Ducting with Insulation	sqft	1360	800	1,088,000	Complete system
4	**HVAC**	HEPA Filter Units (3–4 Ton)	Nos	1	1,500,000	1,500,000	
5	**Electrical**	Ceiling Lights illuminator 48 W Visible surface of the lamp in PVC reflector. Without any extra, cover profile.	Nos	10	9,000	90,000	8–10 beds

6	**Flooring**	**2mm Vinyl Flooring** (ICU + Buffer) Homogenous Floor with self-leveling 2 mm thickness, with a total weight of 3.0 kg/m2 and includes an IQPUR treatment (polyurethane). Installation with an inverted flaw, hot-welded with the same material.	sqft	1360	850	1,156,000	Medical grade
7	**Wall Finish**	1. 2mm MM-Clad UK Original antimicrobial wall cladding with **sub structure:** Galvanized steel Structure frame for OT's with Ceramic Sheet Arish or Elephant	sqft	882	2,500	2,205,000	Hospital grade
8	**Glass Work**	Tempered Glass Chambers (10–12mm)	sqft	300	1,500	450,000	2–3 chambers
9	**Glass Work**	Main Glass Door (7×10)	Nos	70	1,500	105,000	Pivot
10	**Glass Work**	Buffer Double Door (10×8)	Nos	80	1,500	120,000	Entry/Exit
11	**Glass Work**	Glass Chamber Doors	Nos	3	1,500	4,500	
12	**Medical Gas**	ICU Head Units	Nos	10	35,000	350,000	Per bed
13	**Medical Gas**	Oxygen Automatic Manifold System	Set	1	450,000	450,000	3–4 cylinders
14	**ELV**	Public Address System	Set	1	100,000	100,000	Speakers included
15	**ELV**	Fire & Smoke Detection System	Set	1	300,000	300,000	
16	**ELV**	Central Monitoring System (7 Parameter)	Set	1	1,500,000	1,500,000	ICU standard

17	**ELV**	**Anesthesia Pendant** Friction braking system to prevent unintentional movement. • Swiveling arm with 340 degree rotation and with the radius of 750mm • Load capacity up to 110KGS • Electrical Sockets: 08 No's • Gas Outlet: 3 - 5 No's • Shelves: 2 No's (One with Drawer). • Lightweight and robust. • Integrated platforms and drawer unit for individual arrangement of devices of different sizes. **Pak Assembled**	Nos	3	450,000	1,350,000	
18	**Furniture**	ICU BedsStryker FL28EX Electric Hospital Bed – Durable & Ergonomic Design	Nos	10	170,000	1,700,000	If included
19	**Automation**	**S.S. Automatic Sliding door** ● Automatic Hermetically sealed Sliding Door Stainless Steel Grinded and having class 304 with German Motor compliance with EN16005 ● Size: 1450 x 2100 mm. ● Door Frame is also made of Stainless Steel, thickness minimum 1 mm. **Taiwan Drive**	Nos	1	550,000	550,000	Main entrance
		Total				**13,850,500**	

***RATES ARE WITHOUT/EXCLUDING OF ANY TAX (ONLY INCOME TAX INCLUDED)**

TERMS & CONDITIONS: -

Validity:

1. Offered prices are valid for 15 Days.
2. Delivery: Within 45 days after receipt of your confirmed written order & payment transfer in advance.

Payment:

1. 70% Payment advance with Confirm P.O.
2. 20% Payment on delivery of the product at the site.
3. 10% Payment after installation of the complete project.
4. The Offered prices are on a DDP basis & exclusive of all kinds of taxes.
5. Installation: Installation will be provided free of charge. However, all pre-requisites will be provided
6. by the consignee/institute

Warranty: one-year comprehensive warranty from the date of install on.
Transportation charges will be paid separately and are not included in this quotation.

We will be obliged for your Cooperation in this regard.
Thanks & Regards.
Truly yours,

Muhammad Emraan
Admin Manager
0300-2358853
Ahmed@acco.com.pk