To,
Muhammad Shoaib
Assistant Manager . Supply Chain
CRESCENT BAHUMAN LTD

Date: June 02, 2026
Ref No: ACCO/QTSN/1776

SUBJECT: - **QUOTAION FOR REPAIR AND MAINTENANCE WORK OF A SCHOOL BUILDING PINDI BHATTIYAN**

السلام علیکم
Dear Sir,
We are pleased to submit our best quote for subject work as follows: -

Sr.	Description	QTY	Price, PKR	Amount, PKR
1	Quotation for Repair and maintenance work of a school building as per attached BOQ (including masonry, PCC, precast roofing, waterproofing, and finishing works	1	16,281,625.00	16,281,625.00
	Total			**16,281,625.00**

***RATES ARE WITHOUT/EXCLUDING OF ANY TAX (ONLY INCOME TAX INCLUDED)**
TERMS & CONDITIONS: -

1. 50% Advance Payment.
2. Bills shall be paid within 3 days after submission.
3. Payment shall be made on actual measurement.
4. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
5. Water, Electricity shall be provided by the client.
6. Completion time will be decided on agreement.

We will be obliged for your Cooperation in this regard.
Thanks & Regards.
Truly yours,

Tanveer Ahmed
Director
+92-322-8000190
Ahmed@acco.com.pk

Crescent Bahuman Ltd

Engineer Estimate of Repairing of School Building

BOQ

Ser	Description	Unit	Qty	Rate	Amount	Remarks
1	Dismentling of Water Proofing and shifting of Material at designated area.	Sft	13,000	20	260,000	
2	Dismentling of PCC and Brick work and shifting of Material at designated area.	Cft	10,000	40	400,000	
3	Removing of Brick Soiling/ Tuff tiles and shifting of removed material at designated area or directed by the engineer.	Sft	20,000	12	240,000	
4	Providing and laying first-class burnt brick masonry in superstructure up to all floor levels with cement sand mortar (1:4). Includes the cost of providing scaffolding, raking out joints, curing, and all necessary materials, labour, and tools complete in all respects, wall thickness 9".(upto 15ft height)	Cft	2,500	580	1,450,000	
5	Providing and applying cement plaster (1:4) to concrete or masonry surfaces, finished complete. Includes the cost of providing scaffolding, raking out joints, curing, and all necessary materials, labour, and tools complete in all respects	Sft	10,000	68	680,000	
6	Providing and laying 2"to3 thick plain cement concrete (PCC) in flooring using a nominal mix ratio of 1:2:4. The work includes machine mixing, laying in panels or as specified, leveling to proper slope, and finishing the surface smooth with a steel float. The rate shall also include necessary formwork, curing and all labor and tools required to complete the work as per the engineer's direction.	Sft	23,200	160	3,712,000	
7	Supply and fixing of Pre Cast Girder (18"x5")any length as requried **(Replacement of Damaged Girders only Measured as per Actual)** upto 20ft Height, inculding labour Charges, izhar & Banu Mukhtar make only (15 Nos Appox)	Rft	600.00	1,300	780,000	

8	Supply and fixing of Pre Cast Slabs (3.5'x1.5'x1") **(Replacement of Damaged Slabs only Measured as per Actual)** upto 15ft Height, inculding labour Charges, izhar & Banu Mukhtar make only (200~300 Slab Approx)	Sft	1,575.00	195	307,125	
9	Provide and lay water-proofing, insulation on Pre-cast roof, as under, and as per approved by the Engineer. 1) Two (2) Coats of Hot Bitumen (10-20) or Water Proofing chemical (sikka & Ultra only) 2) One Layer of Polythene Sheet 500 micron 3) 2" to 3" Th, Clean Mud Lain in Slope 4) 1-1/2" Th, Brick Tiles Laid with 1:4 C/S 5) Cement Sand mortor 1:3 Grouting	Sft	13,000	375	4,875,000	
10	Providing and applying two coats of approved quality distemper (Nippon & Diamond) on old and new plastered surfaces, including thorough surface preparation such as scraping, sanding, removal of loose paint, dusting, repairing cracks with suitable filler/putty, application of primer on new surfaces or where required on old surfaces, complete in all respects as per specifications and as directed by the Engineer-in-charge.	Sft	42,000	55	2,310,000	
11	Providing and applying two coats of approved quality(Nippon & Diamond) synthetic enamel (oil) paint on borders to old and new surfaces, including thorough surface preparation such as removal of loose/peeling paint, sanding, cleaning, filling cracks and imperfections with suitable putty, and applying primer coat on new surfaces or wherever required on old surfaces, complete in all respects as per specifications and as directed by the Engineer-in-charge.	Sft	19,500	65	1,267,500	
Total					**16,281,625**	