To,
Mr. Salman Bokhari shb
Dha Phase 6, Lahore Punjab

Date: June 04, 2026
Ref #: ACCO/CML/1797

SUBJECT: - **QUOTATION FOR CONSTRUCTION OF GRAY STRUCTURE OF 4 MARLA COMMERIAL** DHA AT LAHORE.

السلام علیکم
Dear Sir,
We are pleased to submit our best quote for subject work as follows: -

SR	SCOPE OF WORK	COVERED AREA	RATE /SFT	AMOUNT (Rs)
1	BASEMENT	900.00	3,800.00	3,420,000
2	GROUND FLOOR	900.00	3,800.00	3,420,000
3	MEZZANINE FLOOR	450.00	3,800.00	1,710,000
4	1ST FLOOR	900.00	3,800.00	3,420,000
5	2nd FLOOR	900.00	3,800.00	3,420,000
6	3rd FLOOR	900.00	3,800.00	3,420,000
7	4th FLOOR	900.00	3,800.00	3,420,000
8	Mumty + Roof	300.00	3,800.00	1,140,000
	TOTAL	**6,150**		**23,370,000**

***RATES ARE WITHOUT/EXCLUDING OF ANY TAX TERMS & CONDITIONS: -**

1. 20% Advance Payment.
2. Bills shall be paid within 3 days after submission.
3. Payment shall be made on actual measurement.
4. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
5. Water, Electricity shall be provided by client.

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE COMMERICAL PLAZA

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Ittefaq /Madina Steel, Sj Seteel, Agha Steel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

We will be obliged for your Cooperation in this regard.
Thanks & Regards.
Truly yours,

Tanveer Ahmed
Director
+92-322-8000190
Ahmed@acco.com.pk