To,
Mr. Rana Waqar Sahab
Lahore, Punjab Pakistan

Date: June 10, 2026
Ref #: ACCO/QTSN/1825

SUBJECT: - QUOTATION FOR CONSTRUCTION OF 4 MARLA COMMERCIAL PLAZA AT LAHORE

السلام علیکم
Dear Sir,
We are pleased to submit our best quote for subject work as follows: -

SR	SCOPE OF WORK	COVERED AREA SFT	RATE /SFT	AMOUNT (Rs.)
1	Gray Structure Construction of 4 Marla Plaza with Basement	6,085	4,800/-	29,208,000/-
	TOTAL	**6,085**		**29,208,000/-**

This total work will cost **Twenty-Nine Million Two Hundred Eight Thousand Only (29,208,000/-Rs)**. Client will pay payment as:

TERMS & CONDITIONS: -

1. Rates of excluding of all Taxes.
2. 20% Advance Payment.
3. Bills shall be paid within 3 days after submission.
4. Payment shall be made on actual measurement.
5. The prices are based on mentioned items. Any additional items shall be claimed separately.
6. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
7. Water, Electricity shall be provided by client.
8. The project timeline shall be mutually agreed upon. Any delays caused by the client, including approvals, site access, or provision of required facilities, may result in revised completion schedules and additional costs.
9. The payment schedule shall be mutually agreed upon before the commencement of work.

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Ittefaq /Madina Steel, Sj Seteel, Agha Steel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

We will be obliged for your cooperation in this regard.
Thanks & Regards.

Tanveer Ahmed
Director