To,
Mr. Majr.
DHA Lahore Punjab

Date: June 12, 2026
Ref #: ACCO/QTSN/1846

SUBJECT: - **QUOTATION FOR DESIGN & CONSTRUCTION OF GRAY STRUCTURE OF 1 KANAL HOUSE** AT DHA LAHORE PUNJAB PAKISTAN.

السلام علیکم
Dear Sir,
We are pleased to submit our best quote for subject work as follows: -

Grey Structure + Design

SR	SCOPE OF WORK	COVERED AREA (SFT)	RATE /SFT	AMOUNT (Rs)
1	INTERIOR & ARCHITECTURE DESIGN OF THE COMPLETE HOUSE INCLUDING CONSTRUCTION, ELECTRICAL, PLUMBING AND STRUCTURE DRAWINGS	7, 200	45.00	324,000.00
2	GRAY STRUCTURE CONTRUCTION OF BASEMENT	1,450	6500.00	9,425,000.00
3	GRAY STRUCTURE CONTRUCTION OF GROUND FLOOR	2,900	3,000.00	8,700,000.00
4	GRAY STRUCTURE CONTRUCTION OF 1ST FLOOR	2,600	3,000.00	7,800,000.00
5	GRAY STRUCTURE CONTRUCTION OF MUMTY	250	3,000.00	750,000.00
	TOTAL	**7,200**		**26,999,000.00**

***RATES ARE WITHOUT/EXCLUDING OF ANY TAX TERMS & CONDITIONS: -**

SR	SCOPE OF WORK	Payment Schedule	
		%age	Amount (Rs)
1	MOBLIZATION ADVANCE	20%	5,335,000.00
2	GROUND FLOOR WALLS UPTO PLINTH	15%	4,001,250.00
3	GROUND WALLS	20%	5,335,000.00
4	GROUND SLAB	20%	5,335,000.00
5	FIRST FLOOR WALLS SLAB	20%	5,335,000.00
6	AFTER COMPLETION OF PROJECT	5%	1,333,750.00
	TOTAL	**100%**	**26,675,000.00**

List of Drawings to be provided

Architectural Drawings + Interior Design:
- 3D Front Elevation
- Furniture Layouts (All Floors)
- Dimensioned Floor Plans (Basement, GF, FF, Mumty)
- Sectional Elevations
- Door/Window Schedules
- Site Demarcation Layout
- Interior Design

Electrical Layouts:
- Electrical Legend + Load Details
- Electrical Wiring Layouts (All Floors)
- DB and Fixture Positions

Public Health (Plumbing) Drawings:
- Water Supply Layouts (All Floors)
- Sewerage Layouts
- Septic Tank and Overhead Tank Details

Structural Drawings:
- Column, Beam, Slab Layouts (All Floors)
- Lintel & Staircase Details
- Septic Tank Design

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Ittefaq /Madina Steel, Sj Steel, Agha Steel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

TERMS & CONDITIONS:

1. Bills shall be paid within 3 days after submission.
2. Payment shall be made on actual measurement.
3. The prices are based on mentioned items. Any additional items shall be claimed separately.
4. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
5. Water, Electricity shall be provided by client.
6. Time of Completion project 6 Months.
7. Design charges 50% will be charges in advance and 50% on completion of the project.

We will be obliged for your Cooperation in this regard.
Thanks & Regards.
Truly yours,

Tanveer Ahmed
Director
+92-322-8000190
Ahmed@acco.com.pk