To,
Mr. Hassan Sahab
Valencia Town Lahore

Date: June 19, 2026
Ref #: ACCO/QTSN/1876

SUBJECT: - **QUOTATION FOR CONSTRUCTION OF GRAY STRUCTURE OF 5 MARLA HOUSE AT VALENCIA TOWN LAHORE.**

السلام علیکم
Dear Sir,
We are pleased to submit our best quote for subject work as follows: -

Grey Strcuture

SR	SCOPE OF WORK	COVERED AREA (SFT)	RATE /SFT	AMOUNT (Rs)
1	HOUSE DESIGN IN VALENCIA TOWN	2,575 sft	35/-	90,125
2	GROUND FLOOR+ FIRST FLOOR + MUMTY(GREY STRUCTURE)	2,575 sft	3,000	7,725,000/-
	TOTAL			**7,725,000/-**

SCOPE OF WORK & MATERIAL DETAILS - CONSTRUCTION OF GREY STRUCTURE HOUSE

SR	SCOPE OF WORK	COMPONENT / SOURCE /BRAND
1	Excavation in Foundation	Manual or by excavator
2	Filling	Ghassu Filling
3	Termite Proofing	Merag/ byflex
4	Brick Ballast	Brick Or Stone Ballast under Flooring
5	Lean Concrete 1:4:8	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
6	P.C.C Concrete 1:2:4 Flooring	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7	**R.C.C Concrete 1:2:4**	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-i	Stair	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
7-ii	Beams & Slab & Lintels	Local Sand, Marghala Crush, Cherat /DG/Maple leaf Cement
8	Steel	Model , Ittefaq /Madina Steel, Sj Seteel, Agha Steel
9	Water Proofing of basement	Water proofing/ Decura water stopper
10	Brick Masonry	1st Class bricks by Pattoki, Local Sand, Cherat /DG/Maple leaf Cement
11	Plaster Internal & External in 1:4	Local Sand, Cherat /DG/Maple leaf Cement

***RATES ARE WITHOUT/EXCLUDING OF ANY TAX TERMS & CONDITIONS: -**

SR	SCOPE OF WORK	Payment Schedule	
		%age	Amount (Rs)
1	MOBLIZATION ADVANCE	20%	1,545,000.00
2	GROUND FLOOR WALLS UPTO PLINTH	15%	1,158,750.00
3	GROUND WALLS	20%	1,545,000.00
4	GROUND SLAB	20%	1,545,000.00
5	FIRST FLOOR WALLS SLAB	20%	1,545,000.00
6	AFTER COMPLETION OF PROJECT	5%	386,250.00
	TOTAL	**100%**	**7,725,000.00**

TERMS & CONDITIONS:

1. Bills shall be paid within 3 days after submission.
2. Payment shall be made on actual measurement.
3. The prices are based on mentioned items. Any additional items shall be claimed separately. Provision of storage facilities for our goods and equipment, where necessary, shall be client responsibility.
4. Water, Electricity shall be provided by client.
5. Time of Completion project 60 working days.
6. Design Payment method 50% in advance.

We will be obliged for your Cooperation in this regard.
Thanks & Regards.
Truly yours,

Tanveer Ahmed
Director
+92-322-8000190
Ahmed@acco.com.pk