To,
M/S. Kishwer Textile Industries (Pvt.) Ltd.
Quaid-e-Azam Business Park, Sheikhupura.

Date: June 24, 2026
Ref#: ACCO/BOQ/1903

SUBJECT: - **QUOTATION FOR BOQ PREPARATION OF TEXTILE INDUSTRIES (PRINTING HALLS & ALLIED BUILDINGS) AT SHEIKHUPURA**

السلام علیکم
We are pleased to submit our best quote for subject work as follows: -

Sr.#	Item Description	Area (SFT)	Rate (Rs.)	Amount
1	Complete BOQ Preparation, Bar Bending Schedule & Rate Analysis (Market Competitive Rates)	Lump Sum	150,000/-	150,000/-
	Total Amount			**150,000/-**

Scope of Work:

The following complete Bill of Quantities (BOQ) package shall be prepared from the provided architectural and structural drawings:

1. Bill of Quantities (BOQ)

- Detailed item-wise BOQ in Excel format, prepared building-wise (Printing Hall-1, Printing Hall-2, Mosque, Guard Room, RMU / Transformer Room, Water Tanks & External Works).
- Complete quantity take-off for all civil trades – earthwork, PCC, RCC (footings, columns, plinth beams, tie beams, roof beams, slabs), masonry, plaster, flooring, finishes, doors / windows / ventilators and external development.
- Each item with description, unit, quantity, rate and amount columns as per standard tender format.
- Quantities derived strictly from the issued drawings and schedules (foundation plan, column & footing sections, beam / slab schedules and door-window schedule).

2. Bar Bending Schedule (BBS)

- Detailed steel reinforcement schedule for all RCC members – footings, columns, plinth beams, tie beams, main & secondary beams, slabs and water tanks.
- Bar marks, diameters, shapes, cutting lengths, number of bars and total weights tabulated by member.
- Steel summary by bar size (#3, #4, #5, #6, #8) and total tonnage for procurement and costing.
- Lap lengths, hooks and bends accounted for as per the general notes / lap length table on the structural drawings.

3. Rate Analysis (Market Competitive Rates)

- Item-wise rate analysis for each BOQ item built up from material, labour, shuttering, transportation, wastage and contractor overhead / profit.
- Rates benchmarked against current Lahore / Sheikhupura market rates (June 2026) – Grade-60 steel, OPC cement, bricks, sand, crush and labour.
- Composite per-unit rates (%Cft / Sft / Kg) suitable for floating the BOQ to multiple contractors for competitive bidding.
- Rate basis and assumptions clearly documented so the client can compare bidder quotes on a like-for-like basis.

Deliverables

- Editable Excel (.xlsx) workbook containing the complete BOQ, Bar Bending Schedule and Rate Analysis.
- Summary sheet with building-wise and grand-total amounts.
- PDF copy for record and circulation to bidders.

Terms & Conditions:

1. The payment will be 50% in advance and 50% on completion of the BOQ.
2. This quotation excludes any tax.
3. Work will start after advance payment.
4. We will be providing the BOQ, Bar Bending Schedule & Rate Analysis in Excel format (with PDF copy).
5. Quantities are based strictly on the drawings provided by the client; any design revision will be charged separately.
6. One round of revision is included; additional revisions will be charged separately.
7. This quotation is valid for 30 days from above mentioned date.
8. BOQ completion time is 10 to 12 working days after advance payment.

We will be obliged for your cooperation in this regard.
Thanks & Regards.
Truly yours,

Tanveer Ahmed
Director
+92-322-8000190